

MAR 16 1994
For corners in

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Allegan County

Located In:

Corner Code #

- 1. Public Land Survey T 3N R 13W E-1 (NE, 5)
T _____ R _____ Monterey Twp.
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

1993 DEC 17 PM 1:56

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21						
7												
8	15	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on October 26, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- E-1 3/4" rod, LCRC Set 3/4" iron over
L2, P92, 5-8-73 stone 1967
- NE 53.83' PP 26" Oak NE 44.7'
- NW 23.54' 32" Oak 22" Oak NNW 22.6'
- S 62.93' PP St. sign NNE 21.95'
- PP SSW 62.50'
- Angle iron E 67.11'
- 2632.24' W to N 1/4 5
- 2652.54' E to N 1/4 4
- 67.32' E to SE 32, 4-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- E-1 Found 1/2" rerod down 10", 0.20' N of line between SE & S 1/4 32 & 67.07' W of SE 32, 4-13
- Set point on line between SE & S 1/4 32 & 67.32' W of SE 32, 4-13
- NE 53.83' PP 22" Oak NNW 22.6'
- NW 23.54' 32" Oak PP SSW 62.50'
- S 62.93' PP
- Meas. W to N 1/4 5, 2632.03'
- Meas. E to SE 32, 4-13
- 67.32' on line between S 1/4 & SE 32, 4-13

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- E-1 Set Set. Allegan Co. Mon. (3/4" x 24" Pin & Cap) down 6"
- Conc. Nail & Allegan Co. Remon. Tag in E side PP S 5° W 62.70'
- Conc. Nail & Allegan Co. Remon. Tag in NW side 8" Pine S 55° W 46.30'
- Conc. Nail & Allegan Co. Remon. Tag in E side 30" Oak N 15° W 23.60'
- Conc. Nail & Allegan Co. Remon. Tag in E side 12" Poplar N 20° E 58.00'
- Conc. Nail & Allegan Co. Remon. Tag in S side PP N 75° E 104.83'
- C/L gravel road S, E 11'±
- C/L gravel road N, E 67.5'±
- On C/L gravel road E-W
- Iron 0.20' N & 0.25' E
- Meas. by hand

Signed by John C. Bueche Date Oct 26, 1993
Surveyor's Michigan License No. 13027

