

**SURVEY
REMONUMENTATION**

APR 29 1998

SECTION

**Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>13W</u>	F-1 (N $\frac{1}{4}$, 4)
	T ___ R ___	<u>Monterey Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

LIBERO 006 PAGES 14

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John C. Bueche, in a field survey on April 13, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

F-1 GLO No information
Did not set corner

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED JUNE 9, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found 1/2" rerod in gravel road on Township Line between (F-13 & E-13) 4-13 and 60.50' West of F-13 (S 1/4, 4-13)
No field division South

Peer group approved 6-9-98.

Traverse 2646.08'

This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 Replaced 1/2" rerod with 3/4" x 36" Pin with Allegan Co. Cap in gravel road
Nail & Allegan Co. Remon. Tag in N side 8" Sass S 75° E 127.07'
Nail & Allegan Co. Remon. Tag in E side 8" Sass S 65° E 101.95'
Nail & Allegan Co. Remon. Tag in W side 14" Elm S 55° E 49.21'
Nail & Allegan Co. Remon. Tag in SW side 10" Sass N 35° E 37.94'
Nail & Allegan Co. Remon. Tag in W side 6" Sass N 60° E 80.37'
Allegan Co. Mon. F-13 (S $\frac{1}{4}$ 34, 4-13) East 60.50'
C/L gravel road E-W is South 6'±



Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 5-8-98

SURVEY
REMONUMENTATION

APR 29 1999

SECTION

A-1
MONTEREY TWP.

LIBERO 006 PAGES 15

