

**SURVEY  
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

**SECTION**

FOR CORNERS IN: ALLEGAN COUNTY	LOCATED IN:	CORNER CODE #
1. Public Land Survey	T3N..... R13W.....	E-5.....
1/4 SEC. COR COMMON TO SEC. 9 & 16 MONTEREY TWP.	T..... R..... T..... R..... T..... R.....	..... ..... .....
2. Property Controlling in section	S..... T..... R..... S..... T..... R.....	..... .....
3. Miscellaneous Property in Sec.	S..... T..... R.....	.....
4. Lot No....., Recorded Plat.....		
5. Private Claims.....		

FILED  
1/28/1999 2:44:39 PM  
JOYCE A. MATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH  
**REGISTER OF DEEDS STAMP & FILE NUMBER**

LIBERO 006 PAGES 16

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Aug. 5, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

\* SEE BACK OF SHEET FOR CORNER HISTORY \*

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED SEPT. 8, 1998  
COUNTY REP. Richard L. Van Ouden

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PER #2, 3, 4, 5, 6, 7, 8, AND 9 ABOVE.  
SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.  
ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

PEER GROUP APPROVED SEPT. 8, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP.
- NAIL & TAG IN NORTH SIDE TELEPHONE POLE S65W 128.10'
- FOUND NAIL IN NORTH SIDE 20' MAPLE S55W 82.40'
- NAIL & TAG IN EAST SIDE 8" MAPLE N70W 62.90'
- C/L STOP SIGN POST S25E 43.55'
- C/L ROAD TO SOUTH WEST 13' +/-
- C/L E & W ROAD NORTH 3' +/-
- TREE & FENCE LINE TO NORTH EAST 3' +/-

Raymond Moored Date 9/18/98  
Surveyors License No. 26463



APR 29 1933

**SECTION**                      **GOVERNMENT CORNER HISTORY**  
**SECTION CORNER COMMON TO SECTIONS 9 & 16**  
**TOWN 3 NORTH, RANGE 13 WEST**  
**F-5**

LIBER 006 PAGES 17

1. G.L.O.

WEST CORRECT LINE BETWEEN SEC 9 & 16  
 40.41 SET QR SEC POST  
 SUGAR 6 IN DIA BEARS S72W 2 LKS  
 SUGAR 13 IN DIA BEARS S40E 26 LKS

2. DOUGLAS W. BONNEMA, MEDEMA, VANKOOTEN & ASSOC., 04-13-72, L.C.R.C. LIBER 1, PAGE 345  
 FOUND NO EVIDENCE OF STONE; RESET WITH  
 1 1/2" SOLID ROD BY HOLDING MID POINT  
 BETWEEN SE COR & SW COR OF SECTION

NAIL IN SIDE 20" MAPLE	SW	82.37'
NAIL IN SIDE TELE. POLE	N-N-NE	36.50'
C/L OF ST. SIGN	N-NW	32.7'
TREE & FENCE LINE TO N.	EAST	3'
C/L GRAVEL ROAD TO S.	WEST	13'

3. D.A. RATEKIN & ASSOCIATES, INC., DONALD RATEKIN, 05-02-75, BOUNDARY SURVEY  
 1 1/2" SOLID ROD

NAIL IN SIDE 20" MAPLE	SW	82.37'
NAIL IN SIDE T. POLE	NNE	36.50'
TREE & FENCE LINE TO NORTH	EAST	3'
C/L GRAVEL ROAD TO SOUTH	WEST	13'
C/L ST. SIGN	NNW	32.7'

(ALSO USED FOR SURVEY OF PARCEL IN S.E. 1/4, 09-12-75)

4. KIRK VAN ORDER, 05-02-79, L.C.R.C LIBER 03 PAGE 257

FD. 1 1/2" SOLID ROD

C/L UNDERGROUND TEL. BOX	SW	54.91'
C/L SOUTH END OF CORR. CULV.	SE	57.03'
C/L NORTH END OF CORR. CULV.	NE	31.53'
NAIL IN SIDE 20" MAPLE	SW	81.37'
C/L GRAVEL ROAD TO SOUTH	W	13.00'
TREE & FENCE LINE TO NORTH	E	3.00'

5. D.A. RATEKIN & ASSOCIATES, INC., JOHN H. DILLINGHAM, 07-07-82, BOUNDARY SURVEY

FD. 1 1/2" IRON

20" MAPLE	SW	82.37'
T. POLE	NNE	36.50'
TELE BOX	SW	54.91'
C/L RD TO SOUTH	WEST	13'

6. WIGHTMAN MOORED, INC., BERYL M. JONES, 02-02-97, BOUNDARY SURVEY

FD. 1 1/2" IRON  
 S59°W 20" MAPLE 82.37'  
 N3°E 3" PIPE 8' LONG 36.70'  
 S4°E STOP SIGN 43.5'  
 S62°W STREET SIGN 45.00'

WITNESS CARDS:

7. HOLLAND ENGINEERING:

1 1/2" SOLID ROD		
CL UNDERGROUND TC BOX	SW	54.91'
CL S END CORR CULV	SE	57.03'
CL N END CORR CULV	NE	31.53'
NAIL SIDE 20" MAPLE	SW	81.37'

8. JONKER:

NAIL IN WEST SIDE OF 8" ELM	N10°E	34.84'
NAIL IN N. SIDE OF 24" MAPLE	S55°W	82.40'
NAIL IN S. SIDE OF 6" ELM	N65°W	97.06'
C/L OF EAST-WEST ROAD NORTH		3'
C/L OF ROAD TO SOUTH	WEST	11'

9. WIGHTMAN MOORED:

1 1/2" SOLID ROD (BONNEMA) REC. 1972		
NAIL IN SIDE 20" MAPLE	SW	82.37'
NAIL IN SIDE TELE. POLE	N-N-NE	36.50'
TREE & FENCE LINE TO N	EAST	3'
C/L GRAVEL ROAD TO S	WEST	13'
C/L OF STREET SIGN	N-NW	32.7'
C/L UNDERGROUND TEL BOX	SW	54.91'
C/L SEND OF CORR. CULV.	SE	57.03'
C/L N END OF CORR. CULV.	NE	31.53'