

SURVEY & REMONUMENTATION

APR 07 1998

**ALLEGAN C. REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION
For corners in Allegan County

<u>ALLEGAN</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T-3N R-13W	✓ F-13. S¼-33
	T R	MONTEREY TWP.
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 J. H. H.

98 JAN 21 PM 1:26

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

I, ARTHUR W. BRINTNALL, in a field survey on 12 JULY 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO.
 WEST SOUTH SIDE SECTION-33, T-3N, R-13W 40.00
 SET QUARTER SECTION POST ON BORDER OF LAKE
 SURVEY IN SOUTHEAST ¼ SECTION 33
 SURVEY IN SOUTHEAST ¼ SECTION-33
 TAMARACK 9 S80E 25
 PINE 26 N89W 70

AUG. 20, 1869
 J.W. HICKS, C.S.
 SHOWS S¼ CORNER
 - NO DESCRIPTION OR WITNESS

(CONTINUED ON BACK OF SHEET)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


F-13
 FOUND CONCRETE MONUMENT WITH CAP (#25867 D.R. PITTS, P.S.) IN LINE WITH
 OLD DOWN FENCE TO NORTH & EAST
 EASTERLY EDGE OF SWAMP EAST 150'±
 FOUND P.K. SOUTHWEST SIDE 18" MAPLE NORTHWEST 18.35'
 FOUND P.K. WEST SIDE 5" COTTONWOOD NORTH-NORTHEAST 5.21'
 FOUND P.K. NORTH SIDE 6" HACKBERRY EAST-SOUTHEAST 9.81'
 FOUND P.K. NORTHWEST SIDE 32" COTTONWOOD SOUTHWEST 15.28'
 FOUND GALVANIZED STEEL FENCE POST NORTHEASTERLY 0.5'±

- REPLACED CAP ON MONUMENT WITH REMON CAP AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.
 - APPROVED BY ALLEGAN PEER GROUP 10 JUNE 97

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 6-10-97
 COUNTY REP. K.V.O.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13
 CONCRETE MONUMENT WITH REMONUMENT CAP
 - IN LINE WITH OLD DOWN FENCE TO NORTH & EAST
 EASTERLY EDGE OF SWAMP E 150'±
 16 D NAIL & REMON TAG SOUTHWEST SIDE 18" MAPLE NORTHWEST 18.35'
 16 D NAIL & REMON TAG WEST SIDE 5" COTTONWOOD NORTH-NORTHEAST 5.21'
 16 D NAIL & REMON TAG NORTH SIDE 6" HACKBERRY EAST-SOUTHEAST 9.81'
 16 D NAIL & REMON TAG NORTHWEST SIDE 32" COTTONWOOD SOUTHWEST 15.28'
 GALVANIZED STEEL FENCE POST NORTHEASTERLY 0.5'±



Signed by Arthur W. Brintnall Date 8-5-97
 PREIN & NEWHOF
 Surveyor's Michigan License No. #28407

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 REVISED OCT., 1995

USER 0006 PAGE 169

APRIL 18, 1972 D.A. RATEKIN, C.S.
L.C.R.C. L-001, P-262
OBVIOUS MISTAKE
- FIRST WITNESS: 7'N OF ROAD CENTERLINE

FEBRUARY 11, 1987 R.E. MOORED, P.S.
WITNESS CARD
SET 3/4" X 6" PIPE WITH CAP (2' EXPOSED) IN FENCE TO NORTH & EAST
EASTERLY EDGE OF SWAMP EAST 150'±
P.K. SOUTHWEST SIDE 15" MAPLE NORTHWEST 18.35'±
P.K. WEST SIDE 3" COTTONWOOD NORTH-NORTHEAST 5.21"
P.K. NORTH SIDE 5" HACKBERRY EAST-SOUTHEAST 9.81
P.K. NORTHWEST SIDE 29" COTTONWOOD SOUTHEAST 15.28
GALVANIZED STEEL FENCE POST NORTHEAST 0.5'±

DECEMBER 12, 1994 D.R. PITTS, P.S.
SURVEY IN SOUTHEAST 1/4 SECTION-33 SHOWS CORNER
NO DESCRIPTION NOR WITNESSES

OCT. 31, 1995 D.R. PITTS, P.S.
SURVEY IN SOUTHWEST 1/4 SECTION-33 SHOWS CORNER
NO DESCRIPTION NOR WITNESSES