

**SURVEY  
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970**

LIBERO 007 PAREO 01

**SECTION**

FOR CORNERS IN:  
ALLEGAN COUNTY

1. Public Land Survey      LOCATED IN:      CORNER CODE #

   T...3N... R...13W      ...G-5.....

   T..... R.....      .....

   T..... R.....      .....

   T..... R.....      .....

SEC. COR COMMON  
TO SEC. 9, 10, 15 & 16  
MONTEREY TWP.

2. Property Controlling  
in section      S.....T.....R.....      .....

   S.....T.....R.....      .....

3. Miscellaneous  
Property in Sec.      S.....T.....R.....      .....

4. Lot No.....Recorded Plat.....

5. Private Claims.....

FILED

1/28/1999 2:44:39 PM

JOYCE A. MATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Aug. 5, 1998 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

\* SEE BACK OF SHEET FOR CORNER HISTORY \*

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED SEPT. 8, 1998  
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" SQUARE IRON BAR IN MON BOX PER #2, 3, 4, 5, 6 AND 7 ABOVE.  
SET 3/4" X 24" ALLEGAN COUNTY REMON IRON W/REMON CAP IN PLACE OF FOUND CORNER.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

PEER GROUP APPROVED SEPT. 8, 1998

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD ALLEGAN COUNTY REMONUMENTATION IRON WITH CAP IN MON BOX.  
-NAIL & TAG IN EAST SIDE POWER POLE S75E - 126.20'  
-NAIL & TAG IN NORTH SIDE 28" MAPLE S80W - 90.50'  
-NAIL & TAG IN EAST SIDE 27" MAPLE S35W - 62.00'  
-C/L STOP SIGN POST S40E - 47.70'

Raymond Moored

Date 9/18/98

Surveyors License No. 26463



SURVEY  
REMONUMENTATION

APR 29 1999

SECTION

GOVERNMENT CORNER HISTORY  
SECTION CORNER COMMON TO SECTIONS 9, 10, 15 & 16  
TOWN 3 NORTH, RANGE 13 WEST  
G-5

1. G.L.O.

80.00 SET POST COR SEC 9, 10, 15 & 16  
A SUGAR 12IN DIA BEARS S. 1 W. 17 LKS DIST  
A SUGAR 14IN DIA BEARS N. 42 E. 18 LKS DIST

2. RATEKIN, 1967, COPY OF CONSUMERS POWER CO. MAP

FOUND IRON 1"  
STREET SIGN NE 53.5'  
CORNER SHED SE 96'  
14" MAPLE SW 40'

3. MEDEMA VAN KOOTEN & ASSOCIATES, 04-13-72, RECORDED SURVEY, LIBER 811 PAGE 611

1" SQUARE IRON IN MONUMENT BOX  
NAIL IN NWLY SIDE 14" MAPLE SW 61.26'  
P.K. IN SELY SIDE TELE. POLE NE 63.96'  
P.K. IN S'LY SIDE TELE. POLE WNW 74.52'  
NW CORNER OF SHED SE 95.9'  
(ALSO RECORDED IN L.C.R.C., LIBER 1 PAGE 345)

4. JOINER ENGINEERING, INC., 04-13-79, RECORDED SURVEY, LIBER 960 PAGE 328

1" SQ IRON IN MON BOX  
NE COR. CONC. SLAB SW 46.60'  
C/L CONC. POST S-11 (101) NE 53.50'  
21" MAPLE SW 61.26'  
NW COR. OF SHED SE 95.90'

5. KIRK VAN ORDER, 05-02-79, RECORDED L.C.R.C. LIBER 3 PAGE 257

FD. 1" SQ. IRON BAR IN MON. BOX  
NE COR. CONC. SLAB SW 46.60'  
CL CONC. POST S-11 (101) NE 53.50'  
21" MAPLE SW 61.26'  
NW COR. SHED SE 95.90'

6. JONKER LAND SURVEY, ROBERT JONKER, 12-06-91, RECORDED L.C.R.C., LIB 4, PG 157

FD. 1" SQUARE PIN IN MON.BOX.  
NAIL N. SIDE 24" MAPLE S80°W 90.67  
NAIL E. SIDE 24" MAPLE S35°W 61.85'  
P.K. N. SIDE FENCE POST N65°E 78.85'  
(ALSO USED ON BOUNDARY SURVEY, DATED 03-08-94)

7. HOLLAND ENGINEERING

FD 1" SQ PIN IN MB RJJ 91  
NAIL N SIDE 24" MAPLE S80W 90.67  
NAIL E SIDE 24" MAPLE S35W 61.85  
PK N SIDE FC POST N65E 78.85

8. WIGHTMAN MOORED

FOUND 1/2" IRON  
ST SIGN NE 53.5'  
CORNER SHED SE 96'  
14" MAPLE SW 40'

LIBER 007 PAGE 02