

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located in:	Corner Code #
1. Public Land Survey	T-3N R-13W T R T R T R	✓ H-13 S-1/4-COR SEC. 34 MONTEREY TWP
2. Property Controlling in Section	S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	

98 JAN 21 PM 1:26  
Register of Deeds  
ALLEGAN COUNTY, MICH.  
*Joyce A. G. [Signature]*

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Arthur W. Brintnall, in a field survey on 17 OCT, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:  
G.L.O. FEB. 6, 1987 R.E. MOORED, P.S.  
WEST ON S SIDE SEC-34, T-3N, R-13W WITNESS CARD  
40.00 SET QR SEC. POST SET 1/2" PIPE @ INT. OF N-S-E

FENCES

- BEECH 10 N 50 E 17
- BEECH 5 N 66 W 46

OLD NOTES FROM PRIOR COUNTY SURVEYOR  
NO DATE

STONE @ S. 1/4 COR SEC-34

- P.K. W. SIDE 21" HICKORY N 16.11
- P.K. NW SIDE 9" ASH SW 19.40

CL 4"x4"x4.5' WOODEN POST E. 0.4'

- P.K. S. SIDE 11" CHERRY WNW 32.14'
- 3/4" ANGLE IRON POST 0.28' N. OF COR.

-IN A 1989 SURVEY MOORED DISREGARDED THIS POSITION  
AND USED STRAIGHT LINE SPLIT  
-DIST BETWEEN G-13 AND I-13 WAS 5303.20'

CONTINUED ON BACK OF CERTIFICATE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
H-13


- FD. 1/2" IRON W/CAP K.V.O #23520
- 1/2 WAY & ON LINE BTWN G-13 & I-13
- FD 16D NE SIDE 22" HICKORY N50°W 56.77
- FD 16D SE SIDE 9" HICKORY S45°W 34.77
- FD 16D SE SIDE 16" OAK S10°W 51.32
- FD 16D E SIDE 18" OAK N05°W 54.47

- ON E'LY EDGE OF WOODS FND NO VISIBLE OCC. TO E&W  
-REPLACED WITH STANDARD ALLEGAN CO. MON. (3/4"x36" IRON W/CAP) AND IS ACCEPTED AS A CAREFUL  
AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER  
-APPROVED BY ALLEGAN CO. PEER GROUP 14 OCT. 97

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 10-14-97  
COUNTY REP. K.V.O.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
H-13

- STD ALLEGAN CO. MON (3/4"x36" IRON W/CAP)
- 16D & REMON TAG NE SIDE 22" HICKORY N50°W 56.80'
- 16D & REMON TAG SE SIDE 9" HICKORY S45°W 34.75'
- 16D & REMON TAG SE SIDE 16" OAK S10°W 51.25'
- 16D & REMON TAG E SIDE 18" OAK N05°W 54.55'
- WETMORE LAKE SOUTH 645±
- H-1 T-2N, R-13W ALLEGAN TOWNSHIP (3/4"x36" IRON W/CAP STD A.C. MON) WEST 4.94'
- G-13 WEST 2651.33
- I-13 EAST 2651.33



Signed by Arthur W. Brintnall Date Nov. 7, 1997

Surveyor's Michigan License No. PREIN & NEWHOF #28407

H-13 MONTEREY (CONTINUED)

## SECTION A CONTINUED

MAR. 5, 1991 K.L. VAN ORDER, C.S.  
SET CAPPED IRON 1/2 WAY AND ON LINE BETWEEN G-13 AND I-13  
18" BITTERNUT WNW 56.77  
9" BITTERNUT SW 34.77  
16" RED OAK SSW 51.32  
11" RED OAK NNW 54.57  
DIST. BETWEEN G-13 AND I-13 WAS 5302.66