

APR 29 1998

SECTION

Allegan County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

LIBERO 007 PAGE 05

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>13W</u>	<u>I-1 (NE, 3)</u> <u>Monterey Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John C. Bueche, in a field survey on April 13, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

I-1 GLO, 1831	LCRC 1-156, Nov., 1971 Bonnema	Survey 869-171 MVK
Lucius Lyon, DS	Re-established obliterated cor. by	June, 1975
38 West set post	existing physical evidence	1/2" solid iron
(25.08')	TP NNW 29.56'	Nail in PP SW 59.7'
Beech 9" S 3	PP SSW 52.80'	PK Nail guard post SE 33.92'
W 33	20" W. Cherry NNE 120.25'	Dist. N 1/4 - NE 40.35 1/2
W. Oak 11" S 46	C/L road East & West, North 10'	
E 65	5/8" solid rod E 25.08'	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1 Found PK on Township Line between (I-13 & H-13) 4-13

All wit. gone

Peer group approved 6-9-98.

Traverse 2639.61'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED JUNE 9, 1998  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1 Replaced PK with 3/4" x 24" Pin with Allegan Co. Cap in bit.  
Nail & Allegan Co. Remon. Tag in W side 12" Elm S 20° W 62.75'  
Nail & Allegan Co. Remon. Tag in N side PP N 80° E 166.82'  
Nail & Allegan Co. Remon. Tag in NW side 12" Elm N 57° E 108.66'  
Nail & Allegan Co. Remon. Tag in S side 12" Cedar N 65° W 77.22'  
SE cor. conc. fnd. to trailer N 18° W 126.45'  
Allegan Co. Mon. in Mon. Box I-13 (SE 34, 4-13) East 17.61'



Signed by John C. Bueche Date 5-8-98  
John C. Bueche, P.S. 13027  
Surveyor's Michigan License No. \_\_\_\_\_

SURVEY  
REMONUMENTATION

APR 29 1933

SECTION

I-1  
MONTEREY TWP.

LIBR0007 PAGE06

