

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|----------------------------|----------------------|
| 1. Public Land Survey | T <u>-3N</u> R <u>-13W</u> | <u>T-3</u> |
| | T _____ R _____ | <u>SE SEC-3</u> |
| | T _____ R _____ | <u>Monterey Twp.</u> |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

1994 DEC 16 AM 9:56
 Register of Deeds
 ALLEGAN COUNTY MICHIGAN
Joyce A. Ebbett

FILED

Register of Deeds Stamp & File Number

I, BASIL ADDRESS, in a field survey on 29 JUN, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO: NORTH BETWEEN SECTIONS 10 & 11
 80.00 SET POST CORNER SECTIONS 2,3,10 & 11
 SUGAR 18 N 59 W 12LKS
 ELM 10 S 40 E 99LKS

J.W. HICKS, C.S.
 1875-DISTANCE WEST TO 1/4 COR 40.41 CHS (2667.06')
 DISTANCE NORTH TO 1/4 COR 40.38 CHS (2665.08')

CONTINUED ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 3/4" PIPE
 CHECKS W/ 1992 KVO WITNESSES
 DIST WEST TO 1/4 COR 2666.96'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 7-12-94
 COUNTY REP. *Hick J. Van Orden*

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED THE 3/4" PIPE W/ STD. ALLEGAN CO. MON. (3/4" X 24" STEEL PIN W/ CAP)

1/2" IRON W/ CAP S 40 W 100.00'
 1/2" IRON W/ CAP S 40 W 200.00'
 NOTE: BOTH IRONS ARE ON SAME LINE TO SEC COR
 16d & REMON TAG SW SDE PP S 40 E 369.38'
 16d & REMON TAG (8' +/- A/G) W SDE PP S 02 E 278.55'
 16d & REMON TAG NW COR RR TIE FE POST N 30 E 47.28'



Signed by *Basil Address* Date 20 AUG 94
 Surveyor's Michigan License No. 30075

REF 0005 PAGE 057

Allegan

A. DESCRIPTION OF ORIGINAL MONUMENT AND/OR SUBSEQUENT RESTORATION.

D.A. RATEKIN, C.S.
1967-FD. 3/4" PIPE
-DIST W TO 1/4 COR 2666.80'
-DIST N TO 1/4 COR 2665.43'
LIES ON E SIDE OF N & S ROADWAY (28TH ST.)
1971-L.C.R.C. L-1, P-34

K.L. VAN ORDER, C.S.
1992-FD. 1 1/4" PIPE
WITNESSES: NAIL IN SE SIDE RAIL FENCE POST ONE 137.18'
C/L TOP MET PED NW 53.46'
C/L TOP MET PED SW 49.27'
NAIL IN SE SDE 22" WALNUT ENE 79.41'
ON EAST SDE N & S GRAVEL RD (28TH ST.)

RECORDED IN THE OFFICE OF THE
CLERK OF THE COUNTY OF ALLEGAN
MICHIGAN
THIS 12th DAY OF MAY 1992
BY THE CLERK