

RE

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P. A. 1970

Joyce A. ...
REGISTER OF DEEDS
ALLEGAN COUNTY

00 FEB -1 AM 8:48

FILED

RECORDED / PAGE 396

SECTION

FOR CORNERS IN: ALLEGAN COUNTY

1. Public Land Survey

LOCATED IN: T. 3N R. 13W CORNER CODE # J-13

SOUTH 1/4 COR. SECTION 35, MONTEREY TWP.

2. Property Controlling in section

3. Miscellaneous Property in Sec.

4. Lot No. Recorded Plat

5. Private Claims

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	34	32	33	34	35	36							
13													

I, Raymond Moored in a field survey on Sept. 23, 1999 do hereby state that under requirements of P.A 74, Michigan P.A of 1970, corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior Bureau of Land management or by a decree of a Court of Law and/or that the corner points mentioned in the lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law established, monumented, recovered, found as expressed below.

Note: Not more than 2 corners, all the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SEE BACK OF SHEET FOR CORNER HISTORY

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND POINTED STONE PER #6 & #7 ABOVE. TRUE CORNER POSITION ON SPLIT OF MILE BETWEEN I-13 AND K-13 WOULD FALL APPROXIMATELY 3.3- FEET TO THE EAST OF FOUND CORNER. EXCAVATED AT THAT LOCATION AND FOUND NOTHING.

REPLACED FOUND CORNER WITH STANDARD ALLEGAN COUNTY REMON IRON AND CAP.

ACCEPTED POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY ALLEGAN COUNTY REMON PEER GROUP ON DEC. 14, 1999.

APPROVED REMONUMENTATION CORNER

P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED DEC. 14, 1999.
COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" X 36" ALLEGAN COUNTY REMON IRON WITH CAP

- FD. NAIL IN N. SIDE 6" OAK S75W 12.37'
- FD. NAIL IN NW SIDE 8" HICKORY S55W 20.95'
- NAIL & TAG IN E. SIDE 8" MAPLE N10W 22.89'
- NAIL & TAG IN SE SIDE 6" OAK S18E 6.25'
- J-1, T.2N., R.13W. WEST 1.68'

Raymond Moored

Date 12/24/99

Surveyors License No. 26463



27

MAR 07 2000

ALLEGAN COUNTY
MONTEREY TOWNSHIP
T.3N., R.13W.

SECTION

J-13

LIBR0007 PAGE 97

A. Description of original monument and accessories and/or subsequent restoration:

1. G.L.O.-WEST SOUTH SIDE SEC 35 T3N R13W
40.00 SET QR SEC POST
BEECH 15 N4E 11
BEECH 9 N61W 11
2. COUNTY SURVEYOR NOTES, (BLACK BOOK)
J-13 TO K-13 = 2667.9'
STAKE
3. COUNTY SURVEYOR, IRA CHICHESTER, APRIL 14TH. 1865
FOUND ORIGINAL WITNESSES AT 1/4 POST ON SOUTH LINE ONE WAS
BROKEN DOWN, MAPLE 16 IN N40°15'W 35
4. COUNTY SURVEYOR, J.W. HICKS, SEPT. 1, 1869
SHOWS S 1/4 CORNER
5. COUNTY SURVEYOR NOTES (BLACK BOOK)
I-13 TO J-13 = 40.05 1/2
J-13 TO K-13 = 40.21
I-13 TO K-13 = 80.265
6. ROBERT J. JONKER, L.C.R.C. REC. LIBER 4, PAGE 56 6-5-89
FOUND POINTED ROCK 1.7' E. OF AXLE SHAFT
NAIL-N. SIDE 6" OAK S75°W 12.37'
NAIL-NW SIDE 8" HICK S65°W 20.95'
NAIL-N SIDE 6" MAPLE N10°W 22.89'
7. HOLLAND ENGINEERING WITNESS CARD
FD. POINTED ROCK JONK 89
NAIL N. SIDE 6" OAK S75W 12.37
NAIL NW SIDE 8" HICKORY S65W 20.95
NAIL N SIDE 6" MAPLE N10W 22.89

