

**SURVEY  
REMONUMENTATION**

APR 29 1999

Allegan County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

**SECTION**

For corners in

|                                       |                          |                      |
|---------------------------------------|--------------------------|----------------------|
| <u>Allegan</u><br>(County)            | Located In:              | Corner Code #        |
| 1. Public Land Survey                 | T <u>3N</u> R <u>13W</u> | <u>K-1 (NE, 2)</u>   |
|                                       | T _____ R _____          | <u>Monterey Twp.</u> |
|                                       | T _____ R _____          | _____                |
|                                       | T _____ R _____          | _____                |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  | _____                |
|                                       | S _____ T _____ R _____  | _____                |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  | _____                |
|                                       | S _____ T _____ R _____  | _____                |
| 4. Lot No. _____, Recorded Plat _____ |                          |                      |
| 5. Private Claims _____               |                          |                      |

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

Register of Deeds Stamp & File Number

LIBERO 007 PAGE 09

I, John C. Bueche, in a field survey on April 13, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 16 |   | 17 |   | 18 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

|   |  |   |
|---|--|---|
| K-1 GLO, 1831<br>Lucius Lyon, DS<br>North Boundary<br>25 lks. West of<br>post<br>Pine 11"<br>S 25 E 16<br>Beech 8"<br>S 25 W 31 | LCRC 1-155, Nov., 1971 Bonnama<br>Re-established obliterated cor. by<br>existing physical evidence<br>Set 1" iron<br>18" Oak SSW 76.94'<br>24" Oak SW 37.88'<br>20" Oak NW 47.54'<br>40" Oak NE 57.79'<br>5/8" solid iron rod E 19.14' | LCRC 1-258, May, 1972 Ratekin<br>Found 1" pipe<br>Nail in 20" Oak N 45° W 47.54'<br>Nail in 40" Oak N 40° E 59.8'<br>24" Oak S 40° W 37.87' |
|---|--|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 Found iron in Mon. Box 0.31' South of Twp. Line between (K-13 & J-13) 4-13  
18" Oak SSW 76.94'±  
24" Oak SW 37.88'±  
Peer group approved 6-9-98.  
Traverse 2653.77'

And is accepted as a careful and faithful perpetuation of the position of the original corner.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED JUNE 9, 1998  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1 Set Conc. Nail & Allegan Co. Remon. Tag on Twp. Line  
Wit. are to nail  
Nail & Allegan Co. Remon. Tag in SE side 28" Oak S 35° W 39.32'  
Nail & Allegan Co. Remon. Tag in NE side PP S 65° E 74.92'  
Nail & Allegan Co. Remon. Tag in N side PP N 50° W 87.06'  
Nail & Allegan Co. Remon. Tag in S side 42" Oak N 74° E 92.42'  
Allegan Co. Mon. in Mon. Box K-13 (SW 36, 4-13) East 19.14'  
Iron in Mon. Box South 0.31'  
On C/L gravel road E; on C/L dr. West; C/L bit. N-S is E. 20'±



Signed by John C. Bueche Date 5-8-98  
John C. Bueche, P.S. 13027  
Surveyor's Michigan License No. \_\_\_\_\_

SURVEY  
REMONUMENTATION

APR 29 1999

SECTION

K-1

MONTEREY TWP.

LIBERO 007 PAGE 10

