

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN <small>(County)</small>	Located in:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>-13W</u>	K-2 (W $\frac{1}{2}$, 1) MONTEREY TWP
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:35
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
Spencer W. Carter

FILED

Register of Deeds Stamp & File Number

**SURVEY &
 REMONUMENTATION**

APR 29 1996

COMMISSION

4. Lot No _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

1. BASIL ANDRESS in a field survey on 16 MAR. 19 95
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as
 expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.


- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|------------------------------|--|
| G.L.O. | NOV., 1971 DOUGLAS W. BONNEMA, P.S. |
| NORTH BETWEEN SECTIONS 1 & 2 | L.C.R.C. L- 001, P- 155 |
| 40.00 SET QR. SEC. POST | REESTABLISHED OBLITERATED CORNER BY |
| BEECH 11" | EXISTING PHYSICAL EVIDENCE. |
| PINE 30" N 75° E 41 LKS | SET 5/8" IRON IN C/L 26TH ST & IN LINE |
| 75.75 TO N BNDRY | W. FE TO EAST |
| | 14" POPLAR ENE 70.50 |
| NO OLD NOTES AVAILABLE | TP SW 93.22' |
| | TP NE 99.23' |

CONT. ON BACK OF CERTIFICATE

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- FD 5/8" IRON
 CHK'S W/ WITNESSES ON L.C.R.S. S
- THIS POSITION IS ACCEPTED AS A CAREFUL AND FAITHFUL REESTABLISHMENT
 OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-14-95
 COUNTY REP. *[Signature]*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- REPLACED 5/8" IRON W/ STD. ALLEGAN CO. MON. (3/4" X 24" PIN & CAP)
 16d & REMON. TAG S. SDE PP N 50° E 99.85'
 16d & REMON. TAG NE SDE 8" CHERRY S 60° E 39.62'
 16d & REMON. TAG SE SDE 8" PINE S 25° W 71.69'
 16d & REMON. TAG S SDE 14" PINE N 55° W 79.76'
 CUT "X" TOP 4" Ø STEEL GATE POST N 75° W 41.92'
 IN C/L 26TH ST.
 IN LINE W/ FE TO EAST
 1/2" IRON "M.V.K." EAST 33.06'



Signed by *Basil J. Andress, Jr.* Date 18 APR 95
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION

APR., 1972 DONALD A. RATEKIN, C.S.
 L.C.R.C. L- 001, P- 25-
 FD 5/8" IRON
 PP S 45° W 93.21
 10" X 10" FE POST E 26.8'
 14" POPLAR N 85° E 70.5'
 PP N 45° E 99.24

APR., 1983 ROBERT J. JONKER, P.S.
 REC'D SURVEY L- 1061, P- 275 & 276
 E 1/2 COR SEC- 2
 1/2" REROD
 NAIL S. SDE POST EAST 32.44'
 MVK IRON EAST 33'
 NAIL W. SDE 10" PINE N 25° W 53.48'
 NAIL S. SDE 8" W. CH. N 85° W 48.56'

WIGHTMAN - MOORED
 WITNESS CARD - NO DATES
 DIST SOUTH TO SW COR - 2667.78'
 DIST NORTH TO NW COR - 2361.43'
 ANGLE ON E. SDE 180°-09'-15"