

REMONUMENTATION

APR 25 1995

COMMISSION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located In:	Corner Code #:
1. Public Land Survey	T-3N R-13W	K-3
	T _____ R _____	SE SEC-2
	T _____ R _____	Monterey Twp.
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	

REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN
James A. Patton

1994 DEC 16 AM 9:56

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, BASIL ANDRESS, in a field survey on 30 JUN, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	19	20	21	22	23	24			
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessions and/or subsequent restoration:
 GLO: NORTH BETWEEN SECTIONS 11 & 12
 80.00 SET POST CORNER SECTIONS 1,2,11 & 12
 BEECH 6 N 89 E 4LKS
 BEECH 14 S 72 W 7LKS

COUNTY SURVEYOR'S OLD NOTES (NO DATE): STAKE & STONE
 BLACK WALNUT 14" NE 80'
 SUGAR MAPLE 12" SE 52.2'

CONTINUED ON BACK OF CERTIFICATE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD. 1 1/4" PIPE OVER 1/2" IRON OVER STONE W/ PIECES OF WOODEN STAKE

THIS CORNER IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 7-12-94
 COUNTY REP. Basil J. Andress

C. Description of monument for corner and accessions established to perpetuate locating the position of the corner:

REPLACED 1 1/4" PIPE, 1/2" IRON & STONE W/ STD. ALLEGAN CO. MON. (3/4" X 24" STEEL PIN W/ CAP)

- MOST N'LY COR CONC FND (HSE #3395) S 40 E 202.27'
- 16d & REMON TAG N SDE 12" LOCUST N 75 E 218.11'
- 16d & REMON TAG NW SDE 20" BOX ELDER N 65 E 79.93'
- SW COR HSE (WOOD TRIM) N 50 E 93.66'
- NE COR CONC FND (HSE #2615) N 40 W 171.59'
- C/L TOP CHAIN LINK FE COR POST N 75 W 142.57'
- 16d & REMON TAG NW SDE 18" MAPLE S 40 W 107.27'



Signed by Basil J. Andress Date 22 AUG 94

Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

HEED 0005 PAGE 055

SHEET 1 OF 2

Allegan

CONTINUED FROM FRONT OF CERTIFICATE

A. DESCRIPTION OF THE ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION:

RECORDED SURVEYS: LIBER-1053, P-70
LIBER-1061, P-275
LIBER-1061, P-289
LIBER-1361, P-155
LIBER-1361, P-157
LIBER-1361, P-159
LIBER-1361, P-161

K.L. VAN ORDER, C.S.
1991-CORNER SHOWN ON SURVEY

L.C.R.C.'S: L-1, P-154
L-1, P-261
L-3, P-325

[Faint, mirrored text, likely bleed-through from the reverse side of the page]