

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>-3N</u> R <u>-13W</u>	<u>L-1 (N$\frac{1}{2}$, 1)</u> <u>MONTEREY TWP</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:35
 REGISTERED FOR 2010
 ALLEGAN COUNTY SURVEY
 Register of Deeds Stamp & File Number

**SURVEY &
 REMONUMENTATION**

APR 29 1996

COMMISSION

4. Lot No _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, BASIL ADDRESS, in a field survey on 16 APR., 19 95
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law, established, re-established, monumented, re-monumented, recovered, found as
expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
CORNER NOT SET BY G.L.O.

OLD NOTES - PREVIOUS COUNTY SURVEYORS
STAKE & PITCH FORK
SHOWS JOG DIST TO EAST OF 14.5 LKS
TO S $\frac{1}{2}$ COR SEC- 36 SALEM TWP
DIST S TO S $\frac{1}{2}$ COR 5027'

1987 RAY MOORED, P.S.
SET 1 $\frac{1}{2}$ " IRON ON TOWNSHIP LINE
9.57' W OF S $\frac{1}{2}$ SEC- 36
C/L 136TH AVE S 7' \pm
OLD ELEC FE TO S IS E 2' \pm
 $\frac{1}{2}$ " IRON W/ CAP S 33.00'
 $\frac{1}{2}$ " IRON W/ CAP E 9.57'
P.K. NW SDE 21" OAK SW 51.70
CUT NAIL SE SDE 33" OAK NE 43.34

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1 $\frac{1}{2}$ " IRON ON TOWNSHIP LINE
CHK'D W/ '87 WITNESSES
FD ANGLE IRON (FALSE COR. PULLED) 2.5' EAST
CHK'D W/ METAL DETECTOR FOR PITCH FORK - NOT INDICATION

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 3-14-95
COUNTY REP. Basil J. Address

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS
MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF
THE CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1 $\frac{1}{2}$ " IRON W/ STD. ALLEGAN CO. MON. (3/4" X 24" PIN & CAP)

16d & REMON TAG W SDE 14" SASSAFRAS N 05° E 83.65'
16d & REMON TAG SE ROOD 18" OAK N 50° E 83.13'
16d & REMON TAG SW SDE 8" PINE S 50° E 54.16'
16d & REMON TAG W SDE 14" OAK S 05° W 65.79'
16d & REMON TAG SE SDE 16" OAK S 40° W 73.30'
16d & REMON TAG NE SDE TWIN 12" OAKS N 65° W 65.99'

C/L 136TH AVE SOUTH 7' \pm
STD ALLEGAN CO. MON (S $\frac{1}{2}$, SEC- 36, SALEM) EAST 9.57'
STD. ALLEGAN CO. MON (SW COR, SEC-36, SALEM) WEST 2633.71'



Signed by Basil J. Address Date 21 APR 95
Surveyor's Michigan License No. 30075

0005 PAGE 253