

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALLEGAN <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T -3N R -13W	L-2 (CEN, 1) MONTEREY TWP
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

1995 DEC 14 PM 2:35
 Register of Deeds Stamp & File Number

FILED

SURVEY &
 REMONUMENTATION

APR 29 1996

COMMISSION

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BASIL ADDRESS in a field survey on 17 MARCH, 19 95
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law, established, re-established, monumented, re-monumented, recovered, found as
 expressed below

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 CORNER NOT SET BY G.L.O.

OLD NOTES (PREVIOUS COUNTY SURVEYORS)
 STAKE
 W. OAK 16" NW 19.9'
 DIST SOUTH TO 1/2 COR - 2649.24'
 DIST NORTH TO 1/2 COR - 2377.76'

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-14-95
 COUNTY REP. [Signature]


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FD 1" PIPE
 L-1 (STD. ALLEGAN CO MON) N 00°-03'-22" W 2361.78'
 M-2 (STD. ALLEGAN CO MON) N 89°-22'-28" E 2652.34'
 L-3 (STD. ALLEGAN CO MON) S 00°-00'-00" W 2649.54'
 K-2 (STD. ALLEGAN CO MON) S 89°-23'-02" W 2653.75'

THIS POSITION NOT ESTABLISHED BY ORIGINAL GOVERNMENT SURVEYORS. THIS
 MONUMENT IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION
 OF THIS CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED 1" PIPE W/ STD. ALLEGAN CO. MON. (3/4" X 36" PIN & CAP)
 16d & REMON TAG E SDE 18" BOX ELDER (4' A/G) S 15° E 327.82'
 16d & REMON TAG E SDE 36" OAK N 35° W 10.26'
 16d & REMON TAG N SDE 18" CHERRY S 80° W 17.68'
 C/L TOP STEEL FE POST 1'± HIGH N 70° W 27.98'
 C/L TOP STEEL FE POST 1'± HIGH N 30° E 22.92'
 C/L 135TH AVE/25TH ST S 45° E 45'±



Signed by [Signature] Date 21 APR 95
 Surveyor's Michigan License No. 30075

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983

0005 PAGE 254

SHEET 1 OF 2

A. DESCRIPTION OF ORIGINAL MONUMENT AND ACCESSORIES AND/OR SUBSEQUENT RESTORATION.

JAN., 1987 RAYMOND MOORED, P.S.
FD 1" PIPE SET ON BI-SECT OF $\frac{1}{2}$ POSTS BY VAN KOOTEN - NO DATE
SQ SPC IN ROOT OF S SDE 28" OAK NNW 9.21'
C/L ST. SIGN SE 12.07'
SQ SPC IN N SDE 8" W CHERRY W 17.71'
C/L GRAVEL RD SE 45'

AUG., 1991 ROBERT J. JONKER, P.S.
FIELD NOTES FOR SURVEY SHOW:
ANGLE W TO S 89°-22'-52"
DIST W TO $\frac{1}{2}$ COR 2653.80'
DIST S TO $\frac{1}{2}$ COR 2649.49'

WIGHTMAN - MOORED (NO DATE)
FIELD NOTES SHOW:
ANGLE E TO S 90°-36'-05"
DIST E TO E $\frac{1}{2}$ COR 2650.60'
DIST S TO S $\frac{1}{2}$ COR 2649.38'