

RE

MAR 07 2000

FILED

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FEB -1 AM 8:40

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>A-12</u> <u>Heath Twp.</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

Jayne L. White
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.

Register of Deeds Stamp & File Number

RECORD 007 PAGE 2914

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L Van Order in a field survey on Nov 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-12

- (1) Not set by GLO
- (2) No other history of corner known

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED Nov. 9, 1999
COUNTY REP. *[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-12

Set corner position midway between A-11 and A-13, T.3N., R.14W. and on line between M-12 and M-13, T.3N., R.15W. Set standard Allegan Co. Remon. monument at this position and this position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner. Peer group approved Nov. 9, 1999. Traversed distance = 2626.36 feet on road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12

Standard Allegan Co. Remon. remonumentation monument (3/4" x 24" steel rod w/red cap #23520)

Nail & Remon. tag in S side 13" b. oak	AZ 265°	70.02'
Nail & Remon. tag in S side 20" b. oak	AZ 95°	57.33'
Nail & Remon. tag in SE side twin 11" w. oak	AZ 50°	69.77'
Nail & Remon. tag in NE side twin 10" w. oak	AZ 290°	44.97'
M-12, T.3N., R.15W. standard Allegan Co. mon.	AZ 00°	23.17'
A-13, T.3N., R.14W. standard Allegan Co. mon.	AZ 180°	2603.195'
C/L sand @ road	AZ 90°	4.5'

Signed by *[Signature]*
Surveyor's Michigan License No. 23520

Date 12-30-1999

