

REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>B-13</u>
	T <u> </u> R <u> </u>	<u>S 1/4 Cor.</u>
	T <u> </u> R <u> </u>	<u>Sec. 31</u>
	T <u> </u> R <u> </u>	<u>Hearth Twp.</u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

REGISTER OF DEEDS
ALLEGAN COUNTY, MICH.
James D. Britton

98 JAN 21 PM 1:23

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Oct. 27, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	15	14	13	12	11	10	9	8	7	6	5	4
7													
8	15	14	13	12	11	10	9	8	7	6	5	4	3
9													
10	30	29	28	27	26	25	24	23	22	21	20	19	18
11													
12	31	30	29	28	27	26	25	24	23	22	21	20	19
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-13
(1) GLO Calvin Britain D.S., Feb. 23, 1832
West S. side of Sec. 31
40.00 ch. Set quarter Sec. post
White Oak 4" N41°E 34 links
Pine 11" N64°W 111 links
GLO West 38.14 chains to A-1, T.2N., R.14W.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 11-11-97
COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13
Kirk L. Van Order Remon. survey dated Oct. 27, 1997
Set B-13 at government prorated distance between C-13 and A-1, T.2N., R.14W. And is accepted as a careful and faithful reestablishment of the position of the original corner.
2615.63' East to C-13
2494.00' West to A-1, T.2N., R.14W.

Peer group approved Nov. 11, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13
Set A.C. Remon monument (3/4" x 36" steel rod w/red plastic cap #23520)
Nail & Remon. tag in SE side 9" Twin B. Oak AZ 25° 99.58'
Nail & Remon. tag in NE side 15" W. Oak AZ 145° 87.00'
Nail & Remon. tag in SE side 19" B. Oak AZ 230° 85.10'
Nail & Remon. tag in NE side 10" Twin B. Oak AZ 330° 91.20'
North edge of asphalt Hwy. M-89 AZ 180° 7.3'

Signed by *Kirk L. Van Order*
Surveyor's Michigan License No. 23520

Date 12-31-97