

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>C-1 (NW,5)</u> <u>Heath Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED  
ALLEGAN COUNTY

97 JAN 22 PM 1:23

FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on Dec. 3, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2		1		
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- C-1  
(1) GLO North between Sec. 5 & 6 84.09 chains to North boundary 63 links East of post and set post corner of Sec. 5 & 6 Hem 6 inch diameter is corner tree 4th Dec. 1831  
(2) Donald A. Ratekin section card info. for Sec. 5, T.3N., R.14W. C-13, T.4N., R.14W. 44.88' West of C-1, T.3N., R.14W. Not set shows distance of 2632.94' between C-1 and D-1 2037.80' East of NW cor. Sec. 5 P.O.T. West bank Sec. 6 (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1  
Kirk L. Van Order remon. survey Dec. 3, 1996  
Set C-1 at 41.58' East of C-13, T.4N., R.14W. as per peer group approved Nov. 26, 1996.

And is accepted as a careful and faithful reestablishment of the position of the original corner.


APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-26-96  
COUNTY REP. Kirk L. Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1  
Set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)  
Nail & Remon. tag in E side 20" R Oak AZ 180° 22.35'  
Nail & Remon. tag in N side 24" R Oak AZ 100° 6.95'  
Nail & Remon. tag in E side 4" R Oak AZ 10° 12.89'  
Nail & Remon. tag in NE side 5" R Oak AZ 335° 8.61'  
In bottom of small gully running SW & NE

Signed by Kirk L. Van Order  
Surveyor's Michigan License No. 23520

Date 12-31-96



158R0005 PAGE 397

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JANUARY 1971  
REVISED MAY 1975  
PROFES REVS. BOARD, 1983  
REVISED OCT., 1985

Section A (continued from Page 1)

C-1

Wash Twp., T.3N., R.14W.

(3) Donald A. Ratekin section card info. for Sec. 6, T.3N., R.14W.  
C-13 44.88' East of C-13, T.4N., R.14W.

(4) Kirk L. Van Order survey rec. L.1243, P.03 NW corner Section  
5, T.3N., R.14W.

6" Ash at corner		
1-1/4" pipe	S89°-50'-52"W	44.88'
23" Oak	E	3.29'
23" Oak	S	22.36'
9" Oak	W,SW	20.93'
Fd. 1/2" iron (DAR)	N89°50'52"E	2037.82'