

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 3N R 14W	✓ D-13
	T R	S 1/4 Cor.
	T R	Sec. 32
	T R	Heath Twp.
2. Property Controlling in Section	S T R	
3. Miscellaneous Property in Sec.	S T R	

98 JAN 21 PM 1:24
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Sept. 4 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13
 (1) GLO Calvin Britain D.S., Feb. 23, 1831
 West S. side of Sec. 32
 40.00 ch. Set quarter post
 Elm 7" N77°E 33 links
 Pine 38" N53-1/2°W 10 links

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 8-12-97
 COUNTY REP. K.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13
 Remon. survey, Sept. 4, 1997, Kirk L. Van Order
 Fd. no evidence of corner and set D-13 midway between E-13 and C-13 on line between E-13 of T.4N., R.14W. and C-1 of T.2N., R.14W. And is accepted as a careful and faithful reestablishment of the position of the original corner.
 Peer group approved Aug. 12, 1997.
 D-13 to D-1 T.2N., R.14W. N88°32'25"E 207.90'
 D-13 to C-1 T.2N., R.14W. S88°32'25"W 2420.49'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13
 Set A.C. Remon. monument (3/4" x 36" steel rod w/red plastic cap #23520)
 Nail & Remon. tag in S. side 12" Maple E., SE 9.37'
 Nail & Remon. tag in S. side 22" Maple NW 0.86'
 3/4" x 36" steel rod in base of tree N25°W 0.71'
 NW corner conc. headwall S72°E 63.47'
 C/L Hwy. M-89 conc. bridge deck over Palmer's Bayou Outlet S64°39'E 117.58'

Signed by Kirk L. Van Order
 Surveyor's Michigan License No. 23520

Date 12-31-97