

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
Allegan (County) Located in: Corner Code #

1. Public Land Survey	T <u>3N</u> R <u>14W</u>	E-11
	T ___ R ___	Sec. 28, 29
	T ___ R ___	32 & 33 Cor.
	T ___ R ___	Heath Twp.
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 1994 DEC 30 PM 12:16
 FILED
Register of Deeds Stamp & File Number

I, Kirk Van Order, in a field survey on February 23, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
6	5	4	3	2	1							
7	6	5	4	3	2	1						
8	7	6	5	4	3	2	1					
9	8	7	6	5	4	3	2	1				
10	9	8	7	6	5	4	3	2	1			
11	10	9	8	7	6	5	4	3	2	1		
12	11	10	9	8	7	6	5	4	3	2	1	
13	12	11	10	9	8	7	6	5	4	3	2	1

A. Description of original monument and accessories and/or subsequent restoration:

E-11
 •80.00 North of E-13 GLO set corner post at Sections 28, 29, 32 & 33
 12" Pine N65°E 10 links
 18" Pine N62½°W 26 links
 •MacDougall in 1910 indicates a stake & stone present at corner. No witnesses indicated.
 •No LCRC

(Continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-11
 Fd. 1" O.D. pipe 18" long using HEI ties listed above.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group approved 3-9-94.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. *Kirk Van Order*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-11
 Replaced pipe with a standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 Nail & Remon. tag in NE side W. Pine S60°E 74.83'
 Nail & Remon. tag in W side 14" W. Oak S10°E 43.65'
 Nail & Remon. tag in E side 18" W. Oak N10°W 34.68'
 Nail & Remon. tag in SE side Tw. 12" W. Pine N30°E 51.66'
 C/L 2-track E & W North 8'+/-

Signed by *Kirk Van Order* Date 12-30-94
 Surveyor's Michigan License No. 23520

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1977
 REVISED MAY 14, 1975
 REVISED JAN., 1983

Section A (continued from Page 1)

E-11

•Holland Engineering, Inc. shows 1" pipe found (no date)

C/L trail	N	8.00'
#14091 tag in 18" Oak	S	7.46'
18" Oak	N,NW	34.66'
18" Oak	NE	28.65'
14" Pine	SE	74.80'

SECTION A
 11/1/54
 11/1/54
 11/1/54