

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

Allegan
(County)

Located in:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>14W</u> | <u>E-13</u> |
| | T ___ R ___ | <u>SE Cor.</u> |
| | T ___ R ___ | <u>Sec. 32</u> |
| | T ___ R ___ | <u>SW Cor.</u> |
| 2. Property Controlling in Section | S ___ T ___ R ___ | <u>Sec. 33</u> |
| | S ___ T ___ R ___ | <u>Heath Twp.</u> |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | _____ |
| | S ___ T ___ R ___ | _____ |

1994 DEC 30 PM 12:15
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
James A. [Signature]

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk Van Order, in a field survey on February 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	15	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-13

- 80.00 West of G-13 GLO set corner post sections 32 & 33
- 16" W. Oak N69°E 31 links
- 20" W. Oak N16°W 9 links
- Old notes, MacDougall, shows Gov. S & S
- 8" Elm N13°W 34.3'
- 6" Elm N29°E 30.44'
- Triple Basswood N34°W 49.65'

- No LCRC
- Ratekin notes show old notes

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13

Fd. stone by using highway right-of-way map and MacDougall's witnesses.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group approved 3-9-94.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13

- Replaced stone with standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
- | | | |
|--|-------|--------|
| Nail & Remon. tag in N side 12" Red Oak | N80°E | 17.28' |
| Nail & Remon. tag in W side 21" Beech | North | 53.03' |
| Nail & Remon. tag in NE side 23" Triple Basswood | N30°W | 49.50' |
| Nail & Remon. tag in NE side 18" Quad Red Oak | North | 23.89' |
| C/L Hwy. M-89 | South | 46.08' |

Signed by [Signature] Date 12-30-94

Surveyor's Michigan License No. 23520

0005 PAGE 088