

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
COMMISSION
 Allegan
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>F-9</u>
	T ___ R ___	<u>N 1/4 Cor.</u>
	T ___ R ___	<u>Sec. 28</u>
	T ___ R ___	<u>S 1/4 Cor.</u>
2. Property Controlling in Section	S ___ T ___ R ___	<u>Sec. 21</u>
	S ___ T ___ R ___	<u>Heath Twp.</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
Jasper L. VanOrder

1993 DEC 30 PM 2:44

FILED

Register of Deeds Stamp & File Number

I, Kirk VanOrder, in a field survey on October 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-9
 •GLO set post @ 39.64 chains
 West of G-9.
 6" Beech N2°W 18½ links
 10" Pine S30½°W 39 links

•D.A.R. survey (L.964, P.527) 4-19-1979

•K.V.O. survey (L.1142, P.527) 4-10-1985

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


F-9
 Found 1½" pipe
 Telephone pole N 36.40'
 16" W. Oak NE 56.25'
 15" Hickory SW 43.85'

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9
 Replaced 1½" pipe with standard Allegan Co. monument (3/4" x 30" steel rod with cap)
 Nail & Allegan Co. Remon. tag in SE side Power Pole NE 90.65'
 Nail & Allegan Co. Remon. tag in E side 9" W. Oak N,NE 92.92'
 Nail & Allegan Co. Remon. tag in NE side 8" Sassafras S,SW 45.80'
 Nail & Allegan Co. Remon. tag in S side 23" W. Oak W,SW 102.42'

Signed by *Kirk L. VanOrder* Date 12-30-93
 Surveyor's Michigan License No. 23520
 LIBER 004 PAGE 326



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983