

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

<u>Allegan</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>F-12</u>
	T ___ R ___	<u>Center</u>
	T ___ R ___	<u>Sec. 33</u>
	T ___ R ___	<u>Heath Twp.</u>
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

James A. C. [Signature]
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN

1994 DEC 30 PM 12:15

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	15	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	●	34	35	36							
13													

I, Kirk Van Order, in a field survey on March 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-12
 •Corner not set by GLO
 •LCRC (L.2, P. 309) 5-22-1974
 1/2" iron
 Iron is on N & S 1/4 line
 Nail in side of 14" Oak S 20.90'
 Nail in side of 8" Oak N,NE 23.16'
 Nail in side of 10" Pine SE 82.17'
 •W-M survey (92-886) 11-20-1992 (L. 1377, P. 835-837)
 •W-M survey (92-972) 12-16-1992

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. Kirk Van Order

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- F-12
 Rd. 5/8" pipe by using info. from LCRC recorded in Liber 2 on Page 309 dated 5-22-1974. Was established using improper procedures and is not utilized in this survey.
 Set monument at intersection of 1/4 lines of Section 33.
 S89°-44'-18"W 2636.47 feet to E-12.
 N89°-44'-18"E 2639.06 feet to G-12.
 N00°-35'-23"E 2632.60 feet to F-11.
 S00°-35'-23"W 2630.81 feet to F-13.
 This position not established by original government surveyors.
 This monument is accepted as the best available evidence of the position of the corner.
 Peer Group approved 3-9-94. 2639.06' on road traverse
7899.88' off road traverse

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-12
 Removed 5/8" pipe
 Set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 Nail & Remon. tag in E side 14" W. Oak N15°W 36.44'
 Nail & Remon. tag in SE side 8" Poplar N20°E 45.43'
 Nail & Remon. tag in E side 13" W. Oak South 45.50'
 Nail & Remon. tag in SW side 14" Jack Pine S50°E 88.98'

Signed by [Signature] Date 12-30-94
 Surveyor's Michigan License No. 23520

REP 0005 PAGE 089