

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

Allegan
(County)

ALLEGAN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Located In:	Corner Code -#
T <u>3N</u> R <u>14W</u>	<u>F-13</u>
T _____ R _____	<u>S 1/4 Cor.</u>
T _____ R _____	<u>Sec. 33</u>
T _____ R _____	<u>Heath Twp.</u>
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

REGISTER OF DEEDS
ALLEGAN COUNTY MICHIGAN

1994 DEC 30 PM 12:16

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Van Order, in a field survey on February 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	14	15	16	17	18							
7													
8	19	20	21	22	23	24							
9													
10	25	26	27	28	29	30							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- F-13
• 40.00 West from G-13 GLO set 1/4 section post.
32" Pine N4°E 43 links
30" Pine N84½°E 65 links
• Gardner notes show stone & 2 unspecified gov. witnesses.
• LCRC (L.2, P. 309) 5-22-1974 Stone
M.S.H.D. tag in side 16" Oak N 27.27' (Continued
Nail in side 12" Oak NE 23.95' on back of
M.S.H.D. tag in side 16" Oak S,SE 25.72' sheet)
S 60.6'
C/L of Hwy. M-89

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13
Fd. stone with punch mark in top using LCRC witness information as listed above.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group approved 3-9-94.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED 3-9-94
COUNTY REP. Paul J. Van Orden

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-13
Replaced stone and set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
Nail & Remon. tag in E side of 20" B Oak N10°E 27.42'
Nail & Remon. tag in SE side of 14" B Oak N60°E 23.94'
Nail & Remon. tag in NE side of 4" Maple S40°E 9.40'
Nail & Remon. tag in N side of 11" W Oak N80°W 27.07'
C/L Hwy. M-89 South 60.6'
C/L steel fence post North 0.35'

Signed by _____
Surveyor's Michigan License No. 23520

Date 12-30-94

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1982

REF: 0005 PAGE 108

Section A (continued from Page 1)

F-13

- Exxel notes show above stone & witnesses..
- Ratekin notes show above stone & witnesses.
- Holland Engineering, Inc. notes show above stone & witnesses.
- W-M survey shows above stone & witnesses (92-886) 11-20-1992

Faint, illegible text, possibly a signature or stamp.