

**SURVEY
REMONUMENTATION**

APR 29 1998

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

SECTION

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>G-4</u>
	T ___ R ___	<u>Hearth Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

LIBERO 006 PAGE 29

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Mar. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-4
- (1) GLO Calvin Britain D.S. 1831
North between Sections 9 & 10
40.00 chains set quarter section post
W. Oak 24" dia. N59°W 27 links
Pine 40" dia. S43°W 48 links
 - (2) LCRC Donald A. Ratekin, L. 2, P. 195, dated June 5, 1973
Set 1" iron on split of distance between NE cor. & SE cor.
(continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- G-4
- Fd. 1" I.D. steel pipe 0.9' long with the following witnesses:
10" W. Oak E,NE 41.83'
And all ties listed in Statement No. 9 field notes

And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved April 14, 1998.

APPROVED REMONUMENTATION CORNER
P.A. 74 OF 1970
ALLEGAN COUNTY
DATE APPROVED APRIL 14, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-4
- Removed fd. 1" pipe and set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 - Nail & Remon. tag in NW side 13" W. Oak AZ 40° 74.81'
 - Nail & Remon. tag in SW side 12" W. Oak AZ 130° 47.84'
 - Nail & Remon. tag in SW side 19" B. Oak AZ 155° 72.98'
 - Nail & Remon. tag in S side 12" W. Oak AZ 265° 38.11'

Signed by [Signature]
Surveyor's Michigan License No. 23520

Date _____



SURVEY
REMONUMENTATION

APR 29 1950

SECTION

LIBRO 005 PAGE 30

Section A (continued from Page 1)

G-4

Heath Twp., T.3N., R.14W.

- (2) Nail in crotch of twin 12" Oaks S45°E 27.10'
C/L trail 6' East
Nail in 14" Oak S40°W 38.09'
In line w/trail to East
Nail in 10" Oak N40°E 25.73'
- (3) D.A. Ratekin & Associates, Inc. recorded survey, L. 840, P. 511, dated June 11, 1973
E. 1/4 post, Sec. 9, T.3.N., R.14W.
Same ties as in No. 2
- (4) LCRC in L. 03, P. 247, by James G. Campbell, dated May 23, 1973
1" iron found
S45E 12" Oak 27.10'
S40W 14" Oak 38.09'
N40E 10" Oak 25.73'
- (5) John Kistler & Associates, James G. Campbell surveyor, recorded survey L. 956, P. 561, dated May 23, 1979
Same tie info. as in No. 4
- (6) Kirk L. Van Order recorded survey L. 1074, P. 231, dated Aug. 13, 1984
Fd. 1" iron pipe
10" W. Oak E,NE 41.83'
13" W. Oak NE 25.82'
18" B. Oak SW 38.08'
10" R. Oak NW 62.22'
- (7) Kirk L. Van Order recorded survey L. 1586, P. 915, dated July 11, 1996
Fd. 1" iron pipe
Same tie info. as in No. 6
- (8) Kirk L. Van Order survey dated July 31, 1996
Fd. 1" iron pipe
Same tie info. as in No. 6
- (9) Kirk L. Van Order survey dated Aug. 7, 1997
Fd. 1" iron pipe
Same tie info. as in No. 6
- Field notes
Fd. 1-1/4" O.D. iron pipe
Fd. nail in S side 12" W. Oak W,SW 38.15'
Fd. nail in SE side 12" W. Oak E,NE 41.87'
Fd. nail in NW side 12" W. Oak NE 74.88'
Fd. bent nail in NE side 15" W. Oak NW 67.49'