

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan
 (County)

Located In:

Corner Code ≠

- | | | |
|---------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>14W</u> | <u>G-6</u> |
| | T _____ R _____ | <u>W 1/4 Cor.</u> |
| | T _____ R _____ | <u>Sec. 15</u> |
| | T _____ R _____ | <u>E 1/4 Cor.</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Sec. 16</u> |
| | S _____ T _____ R _____ | <u>Heath Twp.</u> |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

*Surveyed by Kirk L. Van Order
 11/14/95*

1995 DEC 14 PM 2:33

FILED


**SURVEY &
 REMONUMENTATION**

APR 29 1996

COMMISSION

Register of Deeds Stamp & File Number


I, Kirk L. Van Order, in a field survey on April 4, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:



NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessones and/or subsequent restoration:

- G-6
- GLO North between Sec. 15 & 16
 40.00 set 1/4 section post
 Wh. Oak 12" dia. N57W 18
 Pine 18" dia. S25E 16
 - D.A. Ratekin survey recorded L. 810, P. 29
 E 1/4 post Sec. 16, T.3N., R.14W.
 Indicates setting iron
 14" Oak North 5.6'



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (continued on back of sheet)

G-6
 Kirk L. Van Order dated April 4, 1995
 Fd. capped iron using ties dated Sept. 8, 1992

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved November 14, 1995.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 11-14-95
 COUNTY REP. *[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-6
- Replaced with standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
- | | | |
|---------------------------------------|----------|--------|
| Nail & Remon. tag SE side 11" Bl. Oak | AZ. 35° | 68.95' |
| Nail & Remon. tag N side 9" Wh. Oak | AZ. 85° | 48.57' |
| Nail & Remon. tag N side 8" Wh. Oak | AZ. 105° | 50.12' |
| Nail & Remon. tag SW side 16" Bl. Oak | AZ. 135° | 59.52' |

Signed by *[Signature]* Date 12-13-95
 Surveyor's Michigan License No. 23520

0005 PAGE 218

Section A (continued from Page 1)

G-6

(D.A. Ratekin)

18" Oak East 16.5'

14" Oak S10E 23.1

Witness card E 1/4 post set 1" iron, 1972

●D.A. Ratekin LCRC, L. 01, P. 265, dated Dec. 6, 1971 (same as above ties)

●Thomas E. Joiner LCRC, L. 03, P. 298, dated Oct. 30, 1979

Fd. 1/2" iron bar from former recorded ties

Ties taken:

14" Oak North 5.36'

18" Oak East 16.16'

16" Oak S,SE 22.94'

12" Oak NE 60.87'

●Holland Engineering, Inc. survey recorded L. 984, P. 594, dated April 4, 1980

Fd. 1" iron

14" Oak N 5.6'

18" Oak E 16.5'

14" Oak S10°E 23.1'

●Kirk L. Van Order survey dated June 17, 1987

Fd. 1/2" steel rod

15" Oak N 5.36'

19" Oak E 16.17'

C/L 2-trk. rd. E 10.5'

18" Oak S,SE 22.9'

●Kirk L. Van Order survey dated 1989

Fd. 1/2" re-rod

14" Oak N 5.36'

18" Oak E 16.16'

16" Oak S,SE 22.94'

12" Oak NE 60.87'

●Kirk L. Van Order Sept. 8, 1992 took the following ties prior to road construction

Fd. 1/2" iron

Set nail S side 8" Wh. Oak E,SE 50.00'

Set nail S side 12" Bl. Oak SE 68.50'

Set nail NW side 10" Bl. Oak NE 68.92'

Set nail S side 10" Wh. Oak E,NE 48.61'

●Kirk L. Van Order set capped iron Nov. 18, 1994 after road construction using witness ties above