

MAR 1 1993

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**Allegan** (County)

Located In: Corner Code #

- 1. Public Land Survey T 3N R 14W G-9  
T \_\_\_ R \_\_\_ Secs. 21,  
T \_\_\_ R \_\_\_ 22, 27 & 28  
T \_\_\_ R \_\_\_ Cor.  
2. Property Controlling S \_\_\_ T \_\_\_ R \_\_\_ Heath Twp.  
in Section S \_\_\_ T \_\_\_ R \_\_\_  
3. Miscellaneous S \_\_\_ T \_\_\_ R \_\_\_  
Property in Sec. S \_\_\_ T \_\_\_ R \_\_\_

1993 DEC 30 PM 2:44  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICHIGAN  
*Spencer P. [Signature]*

FILED

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk VanOrder, in a field survey on October 13, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-9
  - GLO set post @ 80.00 chains North of G-11.
  - 28" Pine N42°E 43 links
  - 20" Pine S61°W 33 links
  - D.N.R. notes 1936
  - 6" Stone
  - Corner fence post S 18.2'
  - 24" B. Oak SE 66.6'
  - LCRC (L.2, P.198) 11-14-1973
  - 5/8" iron over 1 1/2" iron bar
  - 12 W. Oak S30°W 21.8'
  - 12 W. Oak S45°W 25.1'
  - 32" B. Oak S50°E 65.9'
  - Power Pole N70°E 81.3'
  - Tw. W. Oak S15°E 64.8'
  - K.V.O. survey (L.1142, P.527) 4-10-1985
  - D.A.R. survey (L.828, P.394) 4-11-1973

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


G-9  
Found 5/8" iron over 1 1/2" iron bar.

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-9  
Replaced 5/8" iron over 1 1/2" iron bar with standard Allegan Co. monument (3/4" x 24" steel rod with cap)
- Nail & Allegan Co. Remon. tag in NE side 37" B. Oak SE 66.93'
- Nail & Allegan Co. Remon. tag in W side 19" Tw. W. Oak S,SE 64.80'
- Nail & Allegan Co. Remon. tag in NW side 10" W. Oak SW 62.07'
- Nail & Allegan Co. Remon. tag in SW side Power Pole W,NW 148.92'
- Nail & Allegan Co. Remon. tag in SE side Power Pole E,NE 147.29'

Signed by [Signature] Date 12-30-93  
Surveyor's Michigan License No. 23520



LIBER 004 PAGE 327