

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>14W</u> | <u>G-12</u> |
| | T _____ R _____ | <u>E 1/4 Cor.</u> |
| | T _____ R _____ | <u>Sec. 33</u> |
| | T _____ R _____ | <u>W 1/4 Cor.</u> |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <u>Sec. 34</u> |
| | S _____ T _____ R _____ | <u>Heath Twp.</u> |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1993 DEC 30 PM 2:44
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
 JAMES L. CHITTS

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk VanOrder, in a field survey on November 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therelore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- G-12
- GLO set post @ 40.00 chains
 - North of G-13.
 - 10" Beech S48°W 25 links
 - 24" Pine S72°E 23 links
 - Fd. W 1/4 post iron 1908 H.M.D.
 - LCRC (L.2, P.109) 8-22-1973
 - 3/4" iron
 - Nail in side 8" Walnut SE 48.51'
 - Nail in side 10" Walnut S,SE 31.21'
 - Nail in side 8" Pine N,NE 53.70'
 - Exxel survey 6-11-1973 #73287
 - Pitts survey 6-3-1981 #81-009
 - K.V.O. survey 4-28-1988 #88-1615
 - W-M surveys: 11-20-1992 #92-886
 12-16-1992 #92-972

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-12
 Fd. 1" x 1 3/4" x 19 1/2" long iron rail 8" below grade.
 Fd. 3/4" I.D. x 18" long pipe 2" below grade, 3.76' S18°20'20"W of rail with E & W 1/4 line assumed bearing of N90°00'00"E.

Removed pipe and dug 1 foot below and found nothing. Also checked with metal locator.

The 3/4" pipe was improperly established and was discounted.

The iron rail is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12
 Replaced iron rail with standard Allegan Co. monument (3/4" x 30" steel rod with red plastic cap).

Nail & Allegan Co. Remon. tag in NE side 14" Walnut	N29°W	83.30'
Nail & Allegan Co. Remon. tag in E side 11" Tree	N04°E	58.86'
Nail & Allegan Co. Remon. tag in SW side 12" Walnut	S46°E	89.15'
Nail & Allegan Co. Remon. tag in NW side 16" Walnut	S37°W	102.21'

Signed by _____ Date 12-30-93
 Surveyor's Michigan License No. 23520

