

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 3N R 14W	G-13
	T ___ R ___	SE Cor.
	T ___ R ___	Sec. 33
	T ___ R ___	SW Cor.
2. Property Controlling in Section	S ___ T ___ R ___	Sec. 34
	S ___ T ___ R ___	Heath Twp.
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1994 DEC 30 PM 12:16
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 J. A. ...
 FILED

Register of Deeds Stamp & File Number

I, Kirk Van Order, in a field survey on March 7, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

G-13
 • 80.00 chains West of I-13 GLO set post
 15" Pine N 50½°W 15 links
 12" W Oak N80°E 28 links
 • LCRC (L. 2, P. 109) 8-22-1973 Bonnema
 Fd. 1/2" Iron
 Nail in side 26" Oak N 4.43'
 M.S.H.D. tag in side 14" Oak NW 24.61'
 Nail in side Dbl. 6" oak NE 22.41'
 C/L Hwy. M-89 South 79.0'

(Continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13
 Fd. 3/4" x 17" pipe by using LCRC tie info. and Van Order survey info. listed above. Also checks with highway right-of-way map of Hwy. M-89.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer Group approved 3-9-94.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 3-9-94
 COUNTY REP. Kirk Van Order

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13
 Replaced pipe with standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
 Nail & Remon. tag in SW side 17" W Oak N70°W 24.62'
 Nail & Remon. tag in SE side 22" B Oak N5°E 4.43'
 Nail & Remon. tag in S side 7" Twin W Oak N60°E 22.40'
 Nail & Remon. tag in NE side 7" B Oak S45°E 24.79'
 C/L 2" O.D. pipe 2' above ground North 0.55'
 C/L Hwy. M-89 South 79.0'

Signed by [Signature] Date 12-30-94

Surveyor's Michigan License No. 23520

0005 PAGE 110

Page 1 of 2

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983