

**SURVEY
REMONUMENTATION**

APR 29 1999

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **SECTION**

<u>Allegan</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>H-3</u>
	T <u> </u> R <u> </u>	<u>Heath Twp.</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH

LIBERO 006 PAGE 33

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Apr. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3								●					
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-3
- (1) GLO
West correct line between Sections 3 & 10
39.90 chains set quarter section post for section
Pine 24" dia. S1°E 50 links
Beech 10" dia. N3°W 39 links
- (2) LCRC by James G. Campbell, Liber 03, Page 247, dated May 23, 1979
Fd. 4" pipe, set 1/2" iron rod over pipe
- (continued on back of sheet)

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY
DATE APPROVED MAY 12, 1998
COUNTY REP. [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- H-3
Fd. 3/4" x 10-1/2" steel rod and capped iron in mon. box and the following accessories:
- | | | |
|---|------|---------|
| Fd. nail & tag #14091 in 4" (now 9") pine | W,NW | 100.57' |
| Fd. nail & tag #14091 in twin 3" oak (now 4") oak | N,NW | 77.90' |
| C/L W. end conc. culvert | SW | 33.90' |
- Determine found irons in mon. box to be false positions approx. 0.4' West and removed irons and mon. box and reset position for corner by found accessories and their dimensions. And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved May 12, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-3
Set standard Allegan Co. Remon. monument (3/4" x 24" steel rod w/red cap #23520) and grouted in with concrete
- | | | |
|---|---------|---------|
| Nail & Remon. tag in NE side 9" scotch pine | AZ 310° | 100.42' |
| Nail & Remon. tag in NE side 6" black oak | AZ 337° | 54.38' |
| Nail & Remon. tag in NE side 11" black oak | AZ 352° | 78.12' |
| Nail & Remon. tag in NW side power pole | AZ 40° | 87.45' |

Signed by [Signature]
Surveyor's Michigan License No. 23520

Date 12



SURVEY
REMONUMENTATION

APR 29 1990

SECTION

LIBERO 006 PAGE 34

Section A (continued from Page 1)

H-3

Heath Twp., T.3N., R14W.

- (Continued No. 2)
- N.5°E. 12" twin maple 32.45'
S.1°E. p. pole 225.92'
- (3) LCRC by Kirk L. Van Order, Liber 03, Page 300, dated Nov. 20, 1979
Fd. 3/8" iron rod
N. edge asphalt rd. North 10.5'
11" black cherry N,NE 32.39'
C/L 2-track rd. South
- (4) Kirk L. Van Order, R.L.S. survey, Liber 1009, Page 407, dated Nov. 30, 1981
Fd. 3/8" iron rod
(same wit. ties as in No. 3)
Plus - p. pole SE 225.92'
- (5) Kirk L. Van Order, R.L.S. survey, Liber 1044, Page 277, dated Apr. 6, 1983
Fd. 3/8" iron rod
(same wit. ties as in No. 3)
- (6) LCRC by David R. Greer, Liber 003, Page 371, dated Nov. 1983
Fd. 1/2" iron
12" cherry North 32.42'
4" pine W,NW 100.57'
Twin 3" oak N,NW 77.90'
Edge asphalt rd. N 10.50'
- (7) Kirk L. Van Order, R.L.S. survey, dated Aug. 27, 1985
Fd. 3/8" iron rod
(same wit. ties as in No. 4)
- (8) Kirk L. Van Order, R.L.S. survey, Liber 1142, Page 548, dated Aug. 29, 1985
Fd. 1" iron in mon. box
C/L tele. ped. SW 47.80'
C/L W. end conc. culv. SW 37.90'
C/L E. end conc. culv. SE 36.95'
N. edge asphalt rd. N 12.7'
S. edge asphalt rd. apron S 14.6'
C/L 2-trk rd South
- (9) Kirk L. Van Order, R.L.S. survey, Liber 1186, Page 187, dated Sept. 5, 1986
Fd. 3/4" iron in mon. box
(same wit. ties as in No. 8 except S. edge of asphalt apron tie)
- (10) Kirk L. Van Order survey dated Dec. 15, 1988
Fd. 3/4" iron in mon. box
(same wit. ties as in No. 9)
- (11) Kirk L. Van Order survey dated July 31, 1996
Fd. capped iron in mon. box
C/L tele. ped. SW 47.90'
C/L W. end culv. SW 33.90'
C/L E. end culv. SE 36.63'