

**SURVEY
REMONUMENTATION**

APR 29 1999

Allegan County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	H-5
	T ___ R ___	Heath Twp.
	T ___ R ___	
	T ___ R ___	
2. Property Controlling in Section	S ___ T ___ R ___	
	S ___ T ___ R ___	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	
	S ___ T ___ R ___	

FILED
1/28/1999 2:44:39 PM
JOYCE A. WATTS
REGISTER OF DEEDS
ALLEGAN COUNTY, MICH
Register of Deeds Stamp & File Number

LIBER 006 PAGE 37

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Apr. 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- H-5
(1) GLO West correcting line between Sections 10 & 15
39.88 chains set quarter section post for section
Pine 12" dia. N85°E 47 links
Pine 16" dia. N21°W 110 links
(2) LCRC by James G. Campbell, Liber 03, Page 247, May 23, 1979
"T" iron set on line midway between SW and SE section corners
South 10" scotch pine 41.02'
S50°E 8" jack pine 40.35' (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-5
Fd. capped iron H.E.I. 1/2" re-rod and the following accessories:
Fd. 10" (now 19") scotch pine South 41.02' (41.24' to fd. nail in W side)
Fd. twin 6" (now 10") white oak NE 53.65' (53.58' to fd. nail in SE side)
And is accepted as a careful and faithful perpetuation of the position of the original corner.
Peer group approved July 14, 1998.

APPROVED REMONUMENTATION CORNER
P.A. 345 OF 1990
ALLEGAN COUNTY

DATE APPROVED JULY 14, 1998
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5
Removed capped iron and set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
Nail & Remon. tag in SE side twin 10" white oak AZ 50° 53.64'
Nail & Remon. tag in NE side 10" jack pine AZ 140° 67.57'
Nail & Remon. tag in W side 19" scotch pine AZ 185° 41.25'
Nail & Remon. tag in SE side 14" scotch pine AZ 205° 41.53'

Signed by [Signature]
Surveyor's Michigan License No. 23520

Date 12-23-98



