

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan
 (County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey | T <u>3N</u> R <u>14W</u> | H-9 |
| | T ___ R ___ | S 1/4 Cor. |
| | T ___ R ___ | Sec. 22 |
| | T ___ R ___ | N 1/4 Cor. |
| 2. Property Controlling in Section | S ___ T ___ R ___ | Sec. 27 |
| | S ___ T ___ R ___ | Heath Twp. |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | |
| | S ___ T ___ R ___ | |

1993 DEC 30 PM 2:44
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN
 [Signature]
 FILED
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk VanOrder, in a field survey on October 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | |
|---|--|
| <u>H-9</u> | •LCRC (L.2, P.198) 2-15-1973 |
| •GLO set post @ 39.99 chains West of I-9. | 1" iron slanted over stone w/punch hole on top |
| 26" W. Oak N58°W 25 links | P. Pole S40°W 40.75' to nail E side |
| 24" Beech S20°W 4 links | 30" Oak S30°E 66.40' to nail W side |
| •D.N.R. 1936 Stone & stake | 26" Tw. Oak N30°E 47.61' " " SE side |
| 14" Maple SW 42.5' | 10" Pine N50°W 52.69' to nail SW side |
| 14" Elm SW 33.6' | •KVO survey 6-29-1987 |
| 12" E. Oak SE 65.8' | •D.A.R. survey (L.828, P.394) 4-11-1973 |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-9
 Found 1" iron over stone with punch hole.


Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9 over
 Replaced 1" iron v stone with standard Allegan Co. monument (3/4" x 24" steel rod with cap)

Nail & Allegan Co. Remon. tag in E side 26" W. Oak	N,NW	97.81'
Nail & Allegan Co. Remon. tag in SE side 32" W. Oak	N,NE	79.22'
Nail & Allegan Co. Remon. tag in SW side 20" Poplar	SE	115.64'
Nail & Allegan Co. Remon. tag in SE side 9" W. Oak	SW	88.84'
Nail & Allegan Co. Remon. tag in SE side Power Pole	SW	40.83'

Signed by [Signature]
 Surveyor's Michigan License No. 23520



Date 12-30-93

LIBER 004 PAGE 323