

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan
 (County)

Located In:

Corner Code H-12

| | | |
|------------------------------------|--------------------------|-------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>14W</u> | <u>H-12</u> |
| | T ___ R ___ | <u>Center</u> |
| | T ___ R ___ | <u>Sec. 34</u> |
| | T ___ R ___ | <u>Heath Twp.</u> |
| 2. Property Controlling in Section | S ___ T ___ R ___ | ___ |
| 3. Miscellaneous Property in Sec. | S ___ T ___ R ___ | ___ |

1893 DEC 30 PM 2:44
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
James L. Roberts

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk VanOrder in a field survey on November 4, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-12
 •No GLO notes found. •LCRC (L.2, P.109) 6-26-1973
 1/2" iron
 NE cor. house SW 134.13'
 •Found rod May 1, 1908, A.M.D. Nail in side 30" Oak E,NE 75.21'
 C/L St. sign SE 32.36'
 •Radio Monitoring Station Dwg. #1 C/L B.T. W 10.0'
 Iron N 2.02'
 •Exxel survey 6-11-1973 #73287 •Ratekin survey 7-23-1976 #76-3306
 •K.V.O. survey 4-28-1988 #88-1615

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-12
 Found capped iron "KVO" 0.71' West of point. Removed.
 Found plow point 18" below grade and 0.50' West of point.
 Found 1" x 2" iron rail 17 1/2" below grade 0.73' West and 0.2' North of point. Left objects in ground.

Set standard Allegan Co. monument at intersection of 1/4 lines.

Accepted as a careful and faithful re-establishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-12
 Set standard Allegan Co. monument (3/4" x 30" steel rod with red plastic cap)
 Nail & Allegan Co. Remon. tag in SE side 17" Sassafras N48°E 83.54'
 Nail & Allegan Co. Remon. tag in S side 38" W. Oak N70°E 73.88'
 Nail & Allegan Co. Remon. tag in SW side 13" Jack Pine S42°E 97.81'
 Nail & Allegan Co. Remon. tag in NW side 18" R. Pine S39°W 114.30'
 Nail & Allegan Co. Remon. tag in NE side 14" R. Pine N52°W 104.56'
 East edge of asphalt pavement W 0.7' +/-

Signed by *[Signature]*
 Surveyor's Michigan License No. 23520



Date 12-30-93

LIBER 004 PAGE 324