

MAR 15 1996

ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
COMMISSION
Allegan
(County)

Located In:	Corner Code #:
1. Public Land Survey	T <u>3N</u> R <u>14W</u> <u>H-13</u>
	T _____ R _____ <u>S 1/4 Cor.</u>
	T _____ R _____ <u>Sec. 34</u>
	T _____ R _____ <u>Heath Twp.</u>
2. Property Controlling in Section	S _____ T _____ R _____
	S _____ T _____ R _____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____
	S _____ T _____ R _____

1993 DEC 30 PM 2:44
REGISTER OF DEEDS
ALLEGAN COUNTY, MICHIGAN
James A. E. [Signature]

FILED

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk VanOrder, in a field survey on November 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- H-13
- GLO set post @ 40.00 chains West of I-13.
- 30" W. Oak N38°W 37 links
- 8" Maple N79½°W 30 links
- H. MacDougall survey notes
- Fd. iron May 1, 1908
- 24" Oak NW 130.7'
- R.O.W. post E,SE 165.8'
- C/L of M-89 S 82.6' (Ties of a later date!)
- LCRC (L.2, P. 109) 6-26-1973
- 1-1/4" iron C/L M-89 S 82.50'
- Nail in side 30" Oak NW 134.75'
- Nail in side 10" Oak NE 104.67'
- Exxel survey 6-11-1973 #73287
- Ratekin surveys: 1-28-1976 #3088, 7-25-1978 #4763, 9-9-1980 #6255
- K.V.O. surveys: 8-27-1984 #452, 4-29-1986 #852, 4-28-1988 #1615

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13
Found 3/4" steel rod.

Accepted as a careful and faithful perpetuation of the position of the original corner.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- H-13
- Unable to remove 3/4" steel rod, capped with red Allegan Co. Remon. cap
- Nail & Allegan Co. Remon. tag in NE side 42" B. Oak N48°W 134.75'
- Nail & Allegan Co. Remon. tag in NW side 14" W. Oak N45°E 104.65'
- Nail & Allegan Co. Remon. tag in SW side 18" W. Oak S30°E 166.61'
- Nail & Allegan Co. Remon. tag in W side 12" W. Oak S17°W 193.59'
- C/L top conc. R/W marker N15°W 138.20'
- C/L top conc. R/W marker N15°E 121.45'

Signed by _____

Surveyor's Michigan License No. 23520

LIBER 004 PAGE 330



12-30-93