

RF

MAR 07 2000

FILED

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FEB -1 AM 8:40

For corners in

Allegan  
(County)

Located in:

Corner Code #

1. Public Land Survey

T 3 N R 14 W

I-2

T \_\_\_ R \_\_\_

Heath Twp.

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER OF DEEDS  
ALLEGAN COUNTY

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk L Van Order in a field survey on Sept 14 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-2

(1) GLO Lucius Lyon, D.S., Nov. 27, 1831  
North between Sections 2 and 3 40 chains set 1/4 section post  
Pine 36" dia. S.57°W. 19 links  
White Oak 10" dia. S.40°E. 42 lks.

(2) LCRC by George Mitchell, dated Feb. 20, 1973, recorded in L.02, P.117  
Found Stone  
8" Oak S.50°W. 18.05'  
4" Pine North 6.55'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: (continued on back of sheet)

I-2

Fd. stone with "x" on top and capped H.E.I. No. 160142 iron below stone using wit. ties from No. 4 of Part A above. Replaced stone and capped iron with a standard Allegan Co. Remon. monument and is accepted as a careful and faithful perpetuation of the position of the original corner.  
Peer group approved Sept. 14, 1999.

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY

DATE APPROVED SEPT. 14 1999  
COUNTY REP. [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-2

Set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)

Nail & Remon. tag in W side 11" w. pine	N10°E	6.46'
Nail & Remon. tag in NE side 15" w. oak	S75°E	21.12'
Nail & Remon. tag in SE side 9" w. oak	S20°W	17.96'
Nail & Remon. tag in N side 35" b. oak	S60°W	27.40'



Signed by Kirk L. Van Order  
Surveyor's Michigan License No. 23520

Date 12-30-1999

LIBERO 007 FILE 299

RF

MAR 07 2000

SECTION

LIBR0007 PAGE300

Section A (continued from Page 1)

I-2

Heath Twp., T.3N., R.14W.

(continued No. 2)

14" Tw oak S.80°E. 21.10'  
Stone is at int. of fence  
To north 4' east

(3) LCRC by David R. Greer, dated Nov. 1983, recorded in L.003, P.372  
Found stone

Oak	S5°W	17.75'
Pine	North	6.55'
Twin Oak	S80°E	21.10'
10" Oak	SE	59.85'
6" Oak	NE	55.98'
36" Oak	SSW	27.40'
C/L Pine	ESE	5.00'

(4) Kirk L. Van Order survey dated Nov. 18, 1997

Found stone with "x" on top

40" red oak	SW	27.36'
11" white pine	N	6.49'
14" white oak	E,SE	21.10'
Fence line N & S	W	5.5'
8" white oak	S,SW	17.93'

(5) Kirk L. Van Order survey dated Nov. 3, 1998.

Found stone with "x" on top  
(same wit. ties as in No. 4)