

**SURVEY  
REMONUMENTATION**

APR 29 1999

**SECTION**

**ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>I-4</u> <u>Heath Twp.</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

FILED

1/28/1999 2:44:39 PM

JOYCE A. WATTS  
REGISTER OF DEEDS  
ALLEGAN COUNTY, MICH

LIBERO006 PAREL 4 1

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on May 1, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4			3		2			1
3													
4	7	8			9			10	●	11			12
5													
6	18	17			16			15		14			13
7													
8	19	20			21			22		23			24
9													
10	30	29			28			27		26			25
11													
12	31	32			33			34		35			36
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4

(1) GLO

North between Sections 10 & 11  
40.00 chains set quarter section post  
W. oak 10" dia. N28°E 12 links  
Pine 12" dia. N70-1/2°W 31 links

(2) Holland Engineering, Inc., no date

Set "T" iron at intersection of old wire fences to N, W & E

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED JULY 14, 1998  
COUNTY REP. [Signature]

(continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4

Fd. steel fence post 2.7' long, top driven flush to ground and the following accessories:

Nail with Tag #14091 in W side 26" (now 39") oak N 12.40'  
Nail with Tag #14091 in N side 10" (now 12") maple E,NE 39.92'  
Nail with Tag #14091 in NE side 10" oak (now stump) SE 38.32'

Also all of wit. ties listed in Part "A", No. 4

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Peer group approved July 14, 1998.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4

Removed steel fence post and set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)

Nail & Remon. tag in W side 39" b. oak AZ 00° 11.97'  
Nail & Remon. tag in S side 6" b. oak AZ 72° 17.17'  
Nail & Remon. tag in W side 12" w. oak AZ 175° 6.05'  
Nail & Remon. tag in NE side 16" maple AZ 295° 38.52'

Signed by [Signature]  
Surveyor's Michigan License No. 23520



Date 12-23-98

SURVEY  
REMONUMENTATION

APR 29 1998

SECTION

LIBERO 006 PAGE 42

Section A (continued from Page 1)

I-4

Heath Twp., T.3N., R.14W.

(Continued No. 2)

- |                                 |      |        |
|---------------------------------|------|--------|
| #14091 in side 26" oak w/old fc | N    | 12.40' |
| #14091 in side 12" maple        | NW   | 39.12' |
| #14091 in side 10" maple        | SW   | 42.95' |
| #14091 in side 10" oak          | SE   | 38.32' |
| #14091 in side 10" maple        | E,NE | 39.92' |
- (3) Kirk L. Van Order, R.L.S. used corner Mar. 23, 1984 for setting center of section. Recorded survey Liber 1074, Page 253. Neither survey or field notes state what is at E. 1/4 corner of Section 10.
- (4) Kirk L. Van Order survey dated Mar. 5, 1998
- |   |      |        |
|---|------|--------|
| Fd. steel fence post, top level with ground |      |        |
| Fd. nail in W. side 12" w. oak              | S,SE | 5.94'  |
| Fd. nail in NE side 16" maple               | NW   | 38.40' |
| Fd. nail & tag in W. side 39" oak           | N    | 12.30' |
| Set nail in S. side 6" b. oak               | E,NE | 17.19' |
| Old fence N. & S.                           | E    | 3'+/-  |