

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
 For corners in

1993 DEC 30 PM 2:45
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICH.
James A. [Signature]

FILED

Allegan (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>I-12</u>
	T ___ R ___	<u>E 1/4 Cor.</u>
	T ___ R ___	<u>Sec. 34</u>
	T ___ R ___	<u>W 1/4 Cor.</u>
2. Property Controlling in Section	S ___ T ___ R ___	<u>Sec. 35</u>
	S ___ T ___ R ___	<u>Heath Twp.</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk VanOrder, in a field survey on November 2, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- I-12
 •GLO set post @ 40.00 chains North of I-13.
 26" Pine S86°E 17 links
 7" Beech N35°W 16 links
- LCRC (L.2, P.108) 8-22-1973
 1/2" iron
 Nail in side 18" Oak W,NW 154.47'
 Nail in side 14" Cherry N,NW 33.61'
 Nail in side 12" Oak NE 131.69'
 On tree line to N & C/L of gravel road

•1874 A. Gardner found stake & witness.

- R.E.M. fd.iron 8-22-84 spike & cap over
 •K.V.O. survey 4-28-1988 #88-1615

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


I-12
 Found R.E.M. capped spike above 1/2" x 18" pipe.

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-12
 Replaced capped spike and pipe with standard Allegan Co. monument (3/4" x 30" steel rod with cap).
 Nail & Allegan Co. Remon. tag in NE side 23" B. Oak N73°W 154.44'
 Nail & Allegan Co. Remon. tag in NE side 17" B. Oak N31°W 85.27'
 Nail & Allegan Co. Remon. tag in W side 6" Sassafras N 67.81'
 Nail & Allegan Co. Remon. tag in SE side 12" W. Oak N55°E 128.34'

Signed by [Signature]
 Surveyor's Michigan License No. 23520



12-30-93

LIBER 004 PAGE 334