

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in 1894

Allegan
 County
 COMMISSION

Heath Township
 Located in: Corner Code #:

1. Public Land Survey	T	3N	R	14W	I-13
	T		R		SW 1/4 Corner
	T		R		of Section 35
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

1993 DEC 17 PM 1:57
 Register of Deeds Stamp & File Number
 J. L. B. B. B.
 REGISTER OF DEEDS
 ALLEGAN COUNTY, MICHIGAN

FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Chris Marschall, in a field survey on July 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

MDOT 92.06' N of Centerline M-89
 GLO set post 80 ch. West of 35-36
 Beech 7" N 71° E 2 L
 Beech 6" N 55 1/2° W 18 L

DA Ratekin 12/5/1979
 1 1/2" Well Point
 PK in NE side 16" Maple S 60° E 13.51'
 Face 6" Pine
 PK W side Twin 12"-10" Oak North 19.33'
 PK SE side Triple 12-10-10 Maple N 30° E 31.82'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Well point from above witnesses 63.37 feet West of closing corner
 I-1. Held as best evidence of perpetuation of true corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard 36" x 3/4" Steel pin into existing well point. Well point is now flush with ground and steel pin is 0.50' above grd.
 J-13 N 90° E 2651.23'
 Measure 63.37' to NW corner section 2 (I-1) Axle shaft which is 0.33' South of True Line: Set 36" x 3/4" Steel pin at 63.37' on Line to J-13
 16" Penny cut Nail W side Twin 16-12 Oak N 06° W 19.15'
 16" Penny cut Nail SE side Triple 14-12-10 Maple N 40° E 31.48'
 16" Penny cut Nail NE side 16" Maple S 61° E 13.76'
 16" Penny cut Nail E side 8" Pine S 10° W 18.31'
 Centerline shallow 3' wide ditch South 21'±
 Centerline M-89 South 92'±
 16" Penny cut Nail S side Twin 20" Maple S 79° W 37.68'
 Centerline top of GTE Box #3997 S 42° E 53.49'

Signed by Chris Marschall Date July 8, 1993

Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 004 PAGE 251

SEE OTHER SIDE

Page 1 of 2