

ALLEGAN COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Allegan
 (County)

Heath Township
 Located In: Corner Code #

- | | | |
|------------------------------------|--------------------------|------------------|
| 1. Public Land Survey | T <u>3N</u> R <u>14W</u> | <u>J-13</u> |
| | T _____ R _____ | South 1/4 Corner |
| | T _____ R _____ | Section 35 |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

1993 DEC 17 PM 1:57
 REGISTER OF DEEDS
 ALLEGAN COUNTY MICHIGAN
 Register of Deeds Stamp & File Number

FILED

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Chris Marschall, in a field survey on July 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- | | |
|---------------------------------|-------------------------------|
| GLO Set post 40 c West of 35-36 | D.A. Ratekin Survey 12/5/1979 |
| W. Oak 20" N 28° W 27 L | "T" Iron and Cap |
| Maple 8" N 79½° W 30 L | 12" Hickory N 08° E 77.73' |
| | 24" Hickory S 79° E 92.85' |
| A. Gardner 10/13/1874 | 18" Hickory S 46° E 33.21' |
| Stake 39.33 C West of 35-36 | 28" Hickory S 49° W 37.74' |

H Mc Dougall - Stone 1905
 Apple 12" NE 55'
 Oak 12" NW 41'

(SEE OTHER SIDE)

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found "T" Iron from above witnesses. Held as Best evidence of perpetuation of true corner.



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Replaced "T" iron with standard Allegan County Monument and Cap and Grouted the upper 3"
- | | |
|-----------------------------------|-----------------------|
| J-1 N90°00'00"E 33.71' | |
| K-13 N90°00'00"E 2612.32' | |
| I-13 N89°16'33"W 2651.23' | |
| 16" Penny cut Nail N side P.P. | S 76° W 111.62' |
| 16" Penny cut Nail NE side 8" Oak | S 51° E 90.71' |
| 1/2" Iron set with C.M. 18661 cap | S 10°9'23"E 40.00' } |
| 1/2" Iron set with C.M. 18661 cap | S 10°9'23"E 110.00' } |
| Centerline E-W Bit. Road North 4' | 1-13 Held as E and W |
| Set Nail & Tag NW side 18" Walnut | N 25°E 57.85' |
| Set Nail & Tag E side 8" Walnut | N 21°W 65.12' |

Signed by Chris Marschall Date July 8, 1993
 Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

SEE OTHER SIDE

LIBE? 004 249

Page 1 of 2