

**ALLEGAN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 3N R 14W	K-9 (SE, 23)
	T R	Heath Twp.
	T R	
	T R	
2. Property Controlling in Section	S - T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

97 JAN 22 AM 1:23
 REGISTERED
 ALLEGAN COUNTY
 FILED
 REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk L. Van Order, in a field survey on Oct. 13, 1993 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	10	9	8	7	6	5	4	3	2	1		
7												
8	13	12	11	10	9	8	7	6	5	4	3	2
9												
10	16	15	14	13	12	11	10	9	8	7	6	5
11												
12	19	18	17	16	15	14	13	12	11	10	9	8
13												

A. Description of original monument and accessories and/or subsequent restoration:

- K-9
- (1) GLO North between Sec. 25 & 26 80.00
 Set Sec. post for Sec. 23, 24, 25 & 26
 Beech 10" dia. S27E 54 links
 Beech 10" dia. N30E 80 links
 - (2) Hugh MacDougall notes early 1900's
 Stake & stone at corner (no witnesses)
 (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- K-9
- | | | |
|--|------|--------|
| Fd. 1/2" capped iron in mon. box | | |
| Fd. pk in 5" Elm | NE | 87.70' |
| Fd. nail in 15" W. Pine | W,NW | 90.81' |
| SE corner conc. box culvert
(measured 59.35') | SW | 59.39' |
| NE corner conc. box culvert | NW | 61.10' |

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED 1-10-95
 COUNTY REP. [Signature]

And is accepted as a careful and faithful perpetuation of the position of the original corner.
 Peer group approved Jan. 10, 1995.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-9
- Removed capped iron and set standard Allegan Co. Remon. monument (3/4" x 36" steel rod w/red cap #23520)
- | | | |
|---|----|---------|
| Nail & Remon. tag in SE side 7" Elm | NE | 87.63' |
| Nail & Remon. tag in NE side 13" W Pine | SE | 104.23' |
| Nail & Remon. tag in S side 10" Maple | NW | 97.76' |
| SE corner conc. box culvert | SW | 59.35' |

Signed by [Signature]
 Surveyor's Michigan License No. 23520

Date 12-31-96



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, 1971
 REVISED MAY 14, 1975
 REVISED JAN. 1983
 REVISED OCT. 1985

USER 0005 PAGE 407

MAY 2 1987

Section A (continued from Page 1)

K-9

Heath Twp., T.3N., R.14W.

- (3) Kirk L. Van Order survey dated July 10, 1987
Set capped iron at corner, by doubling measured
distance 2634.23' from K-11 to K-10, North from K-11 and by
doubling distance 2658.37' from M-9 to L-9, West from M-9
Ties taken:
- | | | |
|--------------------------|------|--------|
| 15" W. Pine | W,NW | 90.81' |
| C/L NE end C.M.P. | NE | 59.72' |
| 4" Poplar | NE | 93.21' |
| C/L Stop & st. sign post | SE | 34.60' |
| C/L SW end C.M.P. | SW | 41.92' |
| C/L Gravel road E & W | N | 7'+/- |
- (4) Wightman-Moored, Inc. project for A.C.R.C. dated Nov. 11, 1988
SW corner Section 24 (witnesses from Co. Surveyor K.V.O.)
15" Pine W,NW 90.81'
(The rest of witness ties gone)
Ties taken:
- | | | |
|------------------------------|----|--------|
| SE corner of conc. box culv. | SW | 59.62' |
| NW corner of conc. box culv. | NW | 69.00' |
- (5) Wightman-Moored, Inc. project for A.C.R.C. dated Dec. 13, 1989
1/2" iron with cap
- | | | |
|-----------------------|------|--------|
| Pk NE side 15" Pine | W,NW | 90.81' |
| Pk SE side 5" Elm | NE | 87.70' |
| NE corner box culvert | NW | 61.10' |
| SE corner box culvert | SW | 59.39' |

0005 408