

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**COMMISSION**  
 Allegan  
 (County)

Heath Township  
 Located In: Corner Code #

1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>K-13</u>
	T _____ R _____	<u>SW Corner</u>
	T _____ R _____	<u>Section 36</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 17 PM 1:56  
 REGISTER OF DEEDS  
 ALLEGAN COUNTY MICHIGAN  
 Register of Deeds Stamp & File Number  
**FILED**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Chris Marschall, in a field survey on July 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Set Post 80 Ch. West of 36
- Beech 12" N 85° E 46L
- W. Oak 26" N 50° W 33L

A. Gardner 1874 Sleigh Shoe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Iron 4.12 feet East of Closing Corner K-1. Held as best evidence of perpetuation of true corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 16 Penny cut Nail W. side 12" Walnut S 13° E 103.89'
- 16 Penny cut Nail E. side 12" Hickory S 09° W 197.49'
- 16 Penny cut Nail N. side P.P. S 66° W 71.25'
- 16 Penny cut Nail SW side 14" Sasafraass S 40° E 63.47'
- K-1 N 90° W 4.12' 0.05 South of line to J-13
- Centerline E-W Bit. North 4.5'±
- Centerline of N-S Gravel Road West 7'±

Found 1/2"x15" Iron Pin and pulled it and set standard Allegan County monument, Grouted top 3"

SEE OTHER SIDE

Signed by Chris Marschall Date July 8, 1993  
 Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983

LIBER 004 PAGE 245

Page 1 of 2