

ALLEGAN COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
 of Surveyors in  
 Michigan

Heath Township  
 Located In: \_\_\_\_\_ Corner Code ## \_\_\_\_\_  
 (County) \_\_\_\_\_

1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>L-13</u>
	T _____ R _____	<u>S 1/4 Cor.</u>
	T _____ R _____	<u>Sec. 26</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

1993 DEC 17 PM 1:56  
 REGISTERED LAND SURVEYOR  
 ALLEGAN COUNTY, MICHIGAN  
 FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Chris Marschall, in a field survey on July 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO set post @ 40 chains West of M-13

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 1 1/2" Pipe on the South side of a Rotted and down, 10" Wood fence corner post with stones set around its base for ballast. Held as best evidence of perpetuation of true corner.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 L-13  
 Set Standard 3/8" x 3/4" Steel Pin inside of 1 1/2" Pipe found on South side of rotted 10" Wood fence post with stones set around base for ballast.  
 16" Penny cut Nail NE side 16" Ash N 25° W 32.31'  
 16" Penny cut Nail E side 10" Maple N 14° E 33.45'  
 16" Penny cut Nail N side 14" Pine S 86° E 16.50'  
 16" Penny cut Nail NE side Twin 8-12 Maple N 59° W 8.95'  
 L-1 East 2.40'

NOTE: Allegan County Remon tag with 16d Duplex Nails were set on October 14, 1993 in line with the cut nails.

Signed by Chris Marschall Date July 8, 1993  
 Surveyor's Michigan License No. 18661

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983