

FILED

RF

MAR 07 2000

ALLEGAN COUNTY REMONUMENTATION

00 FEB -1 AM 8:40

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Allegan</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>M-11</u>
	T ___ R ___	<u>Heath Twp.</u>
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REGISTERED
ALLEGAN COUNTY

REGISTERED
ALLEGAN COUNTY

FILED

FILED

REGISTER OF DEEDS STAMP & FILE NUMBER

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Kirk L Van Order in a field survey on Nov 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

APPROVED REMONUMENTATION CORNER
 P.A. 345 OF 1990
 ALLEGAN COUNTY
 DATE APPROVED Nov. 9 1999
 COUNTY REP. [Signature]

A. Description of original monument and accessories and/or subsequent restoration:

- M-11
- (1) GLO North on East side of Sec. 36 80.00 Set post corner Sections 25 & 36. U.S. Government Deputy Surveyor Lucius Lyon, 1831
 A beech 13 in. dia. S.27W. 12 lks
 A beech 14 in. dia. N.24W. 35 lks
 - (2) D. Ratekin & Assoc. section corner card shows NE corner Sec. 36 (Kistler 1975 W.R.B.)
 Fd. 4 small stones & wood stake, set conc. monument
 (continued on back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-11
- Fd. concrete monument and the following witnesses:
- | | | |
|--------------------------------------|-------|--------|
| Nail in E. side 43" (now 44") w. oak | N.,NW | 64.68' |
| Nail in SW side fence corner post | NW | 69.20' |
| Nail in S. side p. pole | E.,SE | 40.41' |
| Nail in SE side support pole | NE | 77.36' |
- Affixed a red plastic Allegan Co. Remon. cap to top of concrete monument and is accepted as a careful and faithful perpetuation of the position of the original corner.
 Peer group approved Nov. 9, 1999

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11
- Standard Allegan Co. Remon. red plastic cap affixed to the top of a concrete monument
- | | | |
|--|---------|--------|
| Nail & Remon. tag in SE side support pole | AZ 30° | 77.39' |
| Nail & Remon. tag in S side power pole | AZ 105° | 40.40' |
| Nail & Remon. tag in NW side ash | AZ 205° | 96.16' |
| Nail & Remon. tag in SW side fence corner post | AZ 320° | 69.28' |
| 1" x 2" rectangle iron | AZ 00° | 41.78' |

Signed by [Signature]
 Surveyor's Michigan License KIRK L. VAN ORDER 352

Date 12-30-1999



MAR 07 2000

SECTION

Section A (continued from Page 1)

M-11

Heath Twp., T.3N., R.14W.

- (3) 1982 Kirk Van Order survey
 - Fd. conc. monument
 - 50" w. oak NW 64.30'
 - P. pole E.,SE 40.45'
 - Support pole NE 77.33'
- (4) Kirk Van Order survey June 21, 1994
 - Fd. conc. monument
 - Set nail in E. side 43" w. oak N.,NW 64.68'
 - Nail in SW side fence corner post NW 69.20'
 - Nail in S. side power pole E.,SE 40.41'
 - Nail in SE side support pole NE 77.36'
- (5) HEI ties
 - Fd. 4 small stones & wood stake
 - Set conc. monument WRB 75
 - NW cor. sec. 31-3-13 N. 41.79'
 - 30" oak NW 64.70'
 - Guy pole N.,NE 77.30'
 - P.P. E.,SE 40.42'
 - NE corner bldg. fndn. SE 77.35'
 - T.P. SW 69.35'