

SURVEY &  
REMONUMENTATION

APR 07 1998

SECTION

ALLEGAN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Allegan Located In: Corner Code #  
(County)

1. Public Land Survey T R ✓ EF-1  
T R Heath Twp. (#8)  
T R ✓ EF-13  
T R Overisel (Seq. #10)

2. Property Controlling S 4 T 3N R 14W Heath Twp.  
in Section S 33 T 4N R 14W Overisel Twp.

3. Miscellaneous S T R  
Property in Sec. S T R

98 JAN 21 PM 1:24  
REGISTER OF DEEDS  
ALLEGAN COUNTY MICH.  
FILED

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk L. Van Order, in a field survey on Dec. 1, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5		4	3		2		1			
3												
4	7	8		9	10		11		12			
5												
6	18	17		16	15		14		13			
7												
8	19	20		21	22		23		24			
9												
10	30	29		28	27		26		25			
11												
12	31	32		33	34		35		36			
13												

A. Description of original monument and accessories and/or subsequent restoration:

APPROVED REMONUMENTATION CORNER  
P.A. 345 OF 1990  
ALLEGAN COUNTY  
DATE APPROVED 11-11-97  
COUNTY REP. R.V.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Set standard Allegan County witness monument on North and South lines of Section 4, T.3N., R.14W. and Section 33, T.4N., R.14W. respectively on higher lowland on East side of Rabbit River being  
AZ 91°14'02" 601.16 feet from computed position E-1,  
AZ 271°14'02" 2039.35 feet from computed position F-1,  
AZ 91°14'02" 677.06 feet from computed position E-13, and  
AZ 271°14'02" 1957.41 feet from computed position F-13.  
This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.  
Peer group approved Nov. 11, 1997.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Allegan County witness monument (3/4" x 36" steel rod w/yellow cap #23520)  
Nail & Remon. tag in NE side 17" Swamp Oak AZ 105° 13.23'  
Nail & Remon. tag in W side 15" Swamp Oak AZ 175° 12.02'  
Nail & Remon. tag in N side 8" Swamp Oak AZ 230° 10.50'  
Nail & Remon. tag in S side 9" Elm AZ 275° 8.66'  
East edge of Rabbit River AZ 270° 25'+/-  
South edge of Rabbit River AZ 00° 11'+/-

Signed by Kirk L. Van Order Date 12-31-97  
Surveyor's Michigan License No. 23520

