

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Allegan

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T	3N	R	14W	M5
	T	3N	R	14W	M6
	T	3N	R	14W	M7
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

M7 April 06, 1993  
 M6 July 13, 1992  
 M5 July 13, 1993

I, Gary C. Bilow, in a field survey on \_\_\_\_\_, 19\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:  
**M5:** Post established by U.S. Deputy Surveyor L. Lyon in 1830 - accessories: Pine 22 S70W 10 links and Pine 16 N5W 42 links. Found no other records for this corner.  
**M6:** Post established by U.S. Deputy Surveyor L. Lyon in 1830 - accessories: Pine 12 S77W 5 links and Pine 13 S36W 47 links. No other records found.  
**M7:** Post established by U.S. Deputy Surveyor L. Lyon in 1830 - accessories: Pine 36 N34W 13 links and Pine 20 S51W 48 links. Department of Conservation records dated 1-15-1936 (Allegan Dam #1 project) state "Iron - accessories: SW 69.0' 18" Pine stump, NE 28.2' 24" Pine stump, SE 40.0' 24" Pine stump". No other records found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
**M5:** Reestablished corner midway on line between corners M3 and M7 (both recorded this date).  
**M6:** Reestablished corner midway on line between corners M5 and M7 (both recorded this date).  
**M7:** Found 1" Iron bar 1 foot below road surface. No witnesses were recovered. Distance to corner M3 (recorded this date) 10560' per GLO vs 10569.81' measured is reasonable and consistent. Accepted iron bar as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**M5:** Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet 0.7' below road surface  
 S56W 42.00', Nail & Tag in 14" Oak  
 N36W 58.74', Nail & Tag in 20" Oak  
 N47E 21.88', Nail & Tag in 16" Oak  
 S57E 48.75', Nail & Tag in 3" Pine  
**M6:** Set 1/2" x 36" rebar encased in a 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet 0.6' below road surface  
 N56E 41.22', Nail & Tag in 14" Oak  
 S30E 70.16', Nail & Tag in 15" Oak  
 S64W 35.87', Nail & Tag in 9" Oak  
 N84W 28.33', Nail & Tag in 12" Oak  
**M7:** Left 1" Iron bar in place  
 S15E 53.8', Street / Stop sign post  
 S38W 82.88', Double head nail in 11" Oak  
 N9W 34.5', Stop sign post  
 N22W 40.41', Nail in 14" twin Pine

Signed by Gary C. Bilow Date 5/6/93  
 Surveyor's Michigan License No. 26453



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN. 28, 1971  
 REVISED MAY 14, 1975  
 REVISED JAN., 1983