

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Allegan  
(County)

Located In:

Corner Code ~~##~~

1. Public Land Survey	T	<u>3N</u>	R	<u>14W</u>	<u>E8</u>		
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S	<u>20</u>	T	<u>3N</u>	R	<u>14W</u>	<u>6</u>
	S	<u>20</u>	T	<u>3N</u>	R	<u>14W</u>	<u>2</u>
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

2 October 14, 1992  
 E8 September 30, 1992

I, Gary C. Bilow, in a field survey on 6 October 07, 1992, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

E8: Post established by U.S. Deputy Surveyor C. Britain in 1831 - accessories: W. Oak 24, N77E, 24 links and Maple 8, S1W, 36 links.  
 County Surveyor H. MacDougall records in 1907 "Stone - no witnesses." K. Van Order (LS #23520) recorded in field notes dated 1985 "Set capped rebar midway on line between corners E7 and E9 - accessories: 9" White Oak NW 59.02'; 12" Hickory NNW 28.12'; 6" Maple SE 72.23'; 38" W. Oak SW 92.45."  
 6: Corner not established by original government survey. No other records found.  
 2: No previous record for this corner found.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

E8: Found 1/2" capped rebar and all of K. Van Order's witnesses. Accepted this corner as the best evidence of the original GLO post.  
 6: Established corner at the intersection of North-South and East-West 1/8 lines for the Northeast 1/4 of Section 20.  
 2: Found 1/2" rerod midway on line between the Northeast corner and North 1/4 corner. Accepted this iron as the corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

E8: Found 1/2" capped rebar N58W 59.10', Nail in 9" Oak N17W 28.23', Nail in 12" Hickory S17E 72.30', Nail in 6" Maple S56W 92.45', Nail in 38" Oak S32W 6.08', 1/2" rebar 1' deep	6: Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet South 9.07', Spike & Tag in 10" Twin Oak S46W 17.99', Spike & Tag in 5" Pine N45W 21.28', Spike & Tag in 5" Pine North 1'. Steel Fence Post N31W 35.29', 1-1/2" Iron Pipe	2: Found 1/2" rerod N6E 18.84', Spike & Tag in 18" Oak N25E 45.54', Spike & Tag in 14" Oak S23W 34.43', Spike & Tag in 8" Oak N58W 28.45', Spike & Tag in 10" Oak Iron in centerline of East-West trail
---	---	--

Signed by Gary C. Bilow Date 12/15/92  
 Surveyor's Michigan License No. 26453