

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Allegan	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>3M</u> R <u>14W</u>	<u>WC N. of C8</u>
	T <u>3M</u> R <u>14W</u>	<u>WC N. of C9</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Cary C. Bilow, in a field survey on October 14, 1992, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5		4		3		2				
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19	●	20		21		22		23		24	
9			●										
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Line Tree North of C8: Tree on Section line marked by U.S. Deputy Surveyor C. Britain in 1831. Accessory given: North between Sections 19 and 20 - 59.44 Pine 20. No other records found.  
 Line Tree North of C9: Tree on Section line marked by U.S. Deputy Surveyor C. Britain in 1831. Accessory given: North between Sections 19 and 20 - 21.62 Pine 30. No other records found.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Line Tree North of C8: Found Pine stump approximately 32-36" in diameter from General Land Office survey notes call "59.44 Pine 20". Pine tree stump was found to be reasonable and consistent with the measured distance to corner C8. Accepted this tree stump as the original line call.  
 Line Tree North of C9: Found remains of Pine stump approximately 36-40" in diameter from General Land Office survey notes call "21.62 Pine 30". Pine tree stump was found to be reasonable and consistent with the measured distance to corner C8. Accepted this tree stump as the original line call.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Line Tree North of C8: Set 1/2" x 24" capped rebar in center of Pine stump N71E 15.43', Spike & Tag in 9" Oak S14E 12.55', Spike & Tag in 8" Oak S63W 22.26', Spike & Tag in 11" Oak N32W 8.81', Spike & Tag in 5" Oak	Line Tree North of C9: Set 1/2" x 24" capped rebar in center of Pine stump N56W 54.15', Spike & Tag in 8" Pine N38E 47.02', Spike & Tag in Twin 16" Pine and 10" Oak S4E 3.09', Spike & Tag in 11" Oak S67W 13.85', Spike & Tag in 13" Oak West 42', Intersection of North-South-West trails
--	---

Signed by Cary C. Bilow Date 12/15/92  
 Surveyor's Michigan License No. 26453