

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Allegan</u> <small>(County)</small>	Located in:	Corner Code <u>DB</u>
1. Public Land Survey	T <u>3N</u> R <u>14W</u>	<u>DB</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S <u>20</u> T <u>3N</u> R <u>14W</u>	<u>PROP</u>
	S <u>20</u> T <u>3N</u> R <u>14W</u>	<u>PROP</u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Gary C. Bilow, in a field survey on DB October 02, 1992, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

DB: Corner not established by original General Land Office survey. Corner referenced as a stone in old County Surveyor records (not dated) obtained from Wightman and Moored, Inc. Stone not recovered.  
 PROP: No previous record for this corner found.  
 PROP: No previous record for this corner found.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

DB: Corner established at the intersection of the North-South and East-West 1/4 lines.  
 PROP: Corner established midway on line between 1/8 corners #12 and #13.  
 PROP: Established corner midway on line between corner D9 and 1/8 corner #16.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

DB: Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet N32E 7.93', Spike & Tag in 9" Oak S22E 21.55', Spike & Tag in 9" Oak S50W 16.85', Spike & Tag in 7" Cherry N17W 45.61', Spike & Tag in 18" Pine	PROP: Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet N56E 6.72', Spike & Tag in 12" Oak S55E 19.60', Spike & Tag in 10" Oak N15E 24.70', Spike & Tag in 10" Oak S1W 13.35', Spike & Tag in 10" Oak	PROP: Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet S3W 22.07', Spike & Tag in 24" Oak N87E 21.16', Spike & Tag in 13" Oak N52E 10.35', Spike & Tag in 6" Maple South 6.0', Centerline of Trail North 33.00', DNR monument
---	---	---

Signed by \_\_\_\_\_  
 Surveyor's Michigan License No. 26453

