

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF:-	LOCATED IN:-	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 3N S. R. 14W	F-12, F-13
2. PROPERTY CONTROLLED INC. IN SECTION	T. S. R.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R.	
4. FILE NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

**FILED**  
 JUN 11 2 07 PM 1974  
*Henry J. ...*  
 REGISTER OF DEEDS  
 ALBION COUNTY, MICH.  
 REGISTER OF DEEDS STAMP AND  
 FILING NUMBER

I, **Douglas W. Bonnema** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970 the corner points mentioned in lines 1 and 2 above (identified with circles on index sketch diagram) were, in a field survey on May 9, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 1974, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and of subsequent restoration:

*(NOTE) This corner is closest recorded corner on townp. line to east of SE cor. sec. 36 T3N-R15W*

B. Description of corner evidence found and of method applied in restoring or re-establishing corner:  
 F-12 Found 1/2" iron. F-13 Found Stone with "x"  
 No ~~previous~~ previous witnesses. on top. ~~previous~~ previous witnesses. *S 1/4 33*

*3-14 miles East of townp. line (SE 36)*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 F-12 1/2" iron. Iron is on N-S 1/4 line. Nail in sde 14" Oak South 20.90' Nail in sde 8" Oak NNE 23.16' Nail in sde 10" Pine SE 82.17'  
 F-13 Stone. MSHD tag in sde 16" Oak North 27.27' Nail in sde 12" Oak NE 23.95' MSHD tag in sde 16" Oak SSE 25.72' e of M-89 South 60.6'

*These ties check good w/ MDOT 1946 TIES*

SIGNED BY: *Douglas W. Bonnema* DATE: May 22, 1974  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 12579  
 FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_  
 APPROVED AND SIGNED BY: \_\_\_\_\_ DATE: \_\_\_\_\_

