

T3 N. R. 15 W.

I-11 WITNESSES 333 261 281 254
 SW corner section 26, 5/8" iron
 S13°W, 143.90', triple oak, 12", 12", 6"
 N42°W, 70.20', 12" oak
 N73°E, 33.05', 18" oak
 S32°W, 28.76', USGS monument, sta. no. 79Y, 1926

K-10 268 402
 E corner section 26, 3/4" pipe in N-S fence
 S42°E, 7.05', 4" elm, spike
 S08°W, 33.24', 10" maple, spike
 N59°W, 10.94', 18" maple, spike

K-9 285 401
 NE corner section 26, 1" pipe
 N40°E, 22.49', 14" ash, PK & blaze
 S60°E, 14.65', 12" ash, PK & blaze
 S68°W, 52.22', 14" ash, PK & blaze
 N30°W, 54.83', 18" ash, PK & blaze

#1 270
 NW 1/8 corner of NW 1/4 section 26, 1" pipe
 S29°E, 13.44', 11" ash, spike & blaze
 N52°W, 44.70', 8" ash, spike & blaze
 N31°E, 60.39', 5" ash, spike & blaze

#1 271 407
 NE 1/8 corner of SE 1/4 section 26, 1/2" pipe
 S40°W, 4.50', 7" black oak, spike
 East, 13.48', 10" black oak, spike
 N56°W, 4.78', 6" black oak, spike

#1 394 272
 E 1/8 corner of SE 1/4 section 26, 3/4" pipe
 North, 26.08', 10" black oak, spike
 N72°W, 5.61', 5" black oak, spike
 S38°E, 3.67', 4" white oak, spike

#1 394 272
 Point "C" 3/4" pipe
 N80°W, 7.02', 12" black oak, spike
 S40°E, 28.30', 7" white oak, spike
 N70°E, 18.31', 5" white oak, spike

#1 394 272
 Point "F" 3/4" pipe top of high bank S of trail
 S12°E, 12.40', 12" black oak, spike
 S43°W, 10.13', 9" black oak, spike
 N80°E, 12.59', 15" white oak, spike

#1 394 272
 Point "G" 1" pipe top high bank
 N35°E, 8.29', 14" black oak, spike
 S65°E, 14.66', 14" black oak, spike
 S15°E, 13.06', 7" black oak, spike

#1 394 272
 Point "L" 1" pipe in marsh
 N42°E, 73.45', 21" tamarack, spike
 S81°E, 78.60', 12" black cherry, spike
 South, 37.83', 15" ash, spike

I-10 273 297
 NW corner section 26, concrete monument
 WSW, 24.49', 14" red oak
 NE, 12.95', 10" pine
 NW, 3.70', 8" white oak
 ESE, 25.90', 8" white oak

J-11 274 331 260 261
 SW corner section 26, 1 1/2" angle iron
 S10°E, 79.65', 16" oak
 S35°W, 93.50', 20" oak
 N16°W, 31.40', west gate post
 N15°E, 34.30', east gate post
 North, 10.00', E road in line with drive to north and 66' west of fence to north

J-9 290 398 275
 NW corner section 26, 1/2" pipe
 S03°W, 11.44', 7" ash, PK, tag & blaze
 N28°W, 46.72', 10" ash, PK, tag & blaze
 N53°E, 28.60', 5" ash, PK, tag & blaze

#1 276
 N 1/8 corner of NW 1/4 section 26, 1/2" pipe
 S68°W, 102.83', 8" ash, PK, tag & blaze
 N81°W, 100.78', 5" ash, PK, tag & blaze
 N18°E, 70.45', 9" willow, PK, tag & blaze

#9 277 396
 NE 1/8 corner of SE 1/4 section 26, 3/4" pipe
 S75°E, 22.83', 52" willow, PK, tag & blaze
 S57°W, 6.14', 8" willow, PK, tag & blaze
 N90°W, 160.56', 52" willow, PK, tag & blaze
 S57°E, 33.82', 1 1/2" pipe

Point "B" 1" pipe
 N82°W, 14.73', 9" maple, spike
 N49°W, 14.30', 15" white oak, spike
 N03°W, 23.43', 15" basswood, spike
 N59°E, 46.75', 10" white pine, spike
 In south edge trail down high bank

Point "E" 1/2" pipe top of high bank
 S76°E, 4.13', 12" black oak, spike
 N19°W, 14.51', 18" black oak, spike
 N42°E, 21.83', 12" black oak, spike
 S78°E, 8.72', 9" black oak, spike

Point "K" 1" pipe bottom high bank
 N17°W, 7.75', 14" cedar, spike
 N47°E, 4.60', 6" maple, spike
 S79°E, 16.90', 16" hemlock, spike
 East, 26.50', fence