

T. 3 N. R. 15 W.

I-9 SW COR. SEC. 23 - Found 1/2" pipe; replaced with 1" pipe.

282	N32E	14.47'	13" ash	PK, tag & blaze.
400	S22W	32.89'	10" ash	PK, tag & blaze.
299	S83W	75.60'	16" ash	PK, tag & blaze.
293				

I-7 NW COR. SEC. 23 - Found conc. mon. Witnesses are from Kistler survey # 5677 of Dec. 1971.

283	N10W	69.36'	8" black oak	
252	N30E	93.15'	12" black oak	
463	S65E	21.68'	18" white oak	
	South	5.48'	18" black oak	

K-7 NE COR. SEC. 23 - Found conc. mon. Witnesses are from Kistler survey # 5677 of Dec. 1971.

254	South	56.88'	12" black oak	
465	SE	45.89'	18" black oak	
264	NE	81.11'	16" black oak (most Southerly of a group of three)	
	N10E	94.93'	12" white oak	

K-9 SE COR. SEC. 23 - Set 1" x 5' pipe.

285	N40E	22.49'	14" ash	PK & blaze.
401	S60E	14.65'	12" ash	PK & blaze.
269	S68W	52.22'	14" ash	PK & blaze.
	N30W	54.83'	18" ash	PK & blaze.

#10 W1/8 COR., SW1/4 SEC. 23 - Set 1" pipe.

403	N38E	22.24'	8" ash	PK, tag & blaze.
286	S40E	14.31'	4" willow	PK, tag & blaze.
	S54W	13.93'	8" willow	PK, tag & blaze.